

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX No. P-2

History of original corner establishment:

Baker County Survey Records show no previous establishment of this corner.

DIAGRAM
T11S R41E
W1/16
C.-C
S19
1989
PLS 848

Description of corner evidence found:

Baker County Survey Records show no previous establishment of this corner.

Description of monument and accessories I established to perpetuate the original location of this corner:
Set aluminum pipe with 3-1/2" aluminum cap, stamped as shown on the DIAGRAM, Set 27" in the ground.

From Which:

Set 1/2"x24" iron pins with aluminum caps, as follows:
S53 48'E., 10.4 ft., stamped: C-W 1/16 S19 ,RM and an arrow with course to the corner and 1989, PLS 848.
S44 23'W., 90.46 ft., stamped C-W 1/16 S19, RM and an arrow with course to the corner and 1989, PLS 848. This Pin is part of the survey control network. Set a steel post with warning sign Measurements to pins taken with electronic tachimeter with angles turned from the survey control network. Set steel fence posts with Warning and Boundary signs 5 ft. North & 4 ft. East from the monument.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JULY 12, 1933
DOUGLAS M. FERGUSON
848

This work is performed by:
Douglas M. Ferguson PLS 848
D.Mitchell Ferguson & Ken H. Delano
On Nov.30 ,1989
Refer to Baker Co. Survey No.11-41 -1

Office of _____ County of _____
State of _____ I hereby certify that the within instrument was filed
in this office for record on the _____ day of _____, 19____
_____ by _____
(COUNTY OFFICIAL) (DEPUTY)

FILED Jan 4 1991
BAKER COUNTY SURVEYOR
SURVEY NO. 11-41-8