

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX No. P-5

History of original corner establishment:
Corner was originally established in 1874
by Benjamin Vaughan, under General Land
Office Contract No. 211. Surveyor General
notes state: Set stone 14x10x8 for 1/4
sec. corner.

DIAGRAM
1/4
S19;S20
T11S R41E
1960
(BLM CAP)

In 1960, C. Albert White, Cadastral Surveyor for The Bureau Of Land
Managment, under special instructions, group No. 261, dated Sep. 3,
1940, approved Jan. 16, 1941, and assignment instructions dated
May 5, 1960, re-monumented this corner at proportionate distance.

Description of corner evidence found:

Found 2-1/2" iron pipe with 3" brass cap stamped as shown in the
DIAGRAM. Corner monument is solid and in good condition.
Found bearing tree as established by C. Albert White
Fir 15 ins. diam. bears N83E, 5.4 ft., healed blaze.
Fir 12 ins. diam. bears N69W, 36.3 ft., healed blaze.

Description of monument and accessories I established
to perpetuate the original location of this corner:

W. Fir 12" Diam. bears S36E, 25.1 ft., scribed 1/4 S20 BT.
Set 1/2" x 24" iron pins with aluminum caps as follows:
S82-50'W, 216.85 ft., stamped 1/4 S19, RM with an arrow and course to
the corner. This pin is part of the survey control network. Set a
steel post with warning sign along side this pin.
Measurements to pin taken with electronic tachimeter with angles
turned from the survey control network.
Set steel post with warning sign 4' West.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JULY 12, 1969
DOUGLAS M. FERGUSON
848

This work is performed by:
Douglas M. Ferguson PLS 848
D. Mitchell Ferguson & Ken H. Delano
On June 11, 1990
Refer to Baker Co. Survey No. 11-41-1

Office of _____ County of _____
State of _____ I hereby certify that the within instrument was filed
in this office for record on the _____ day of _____, 19____

(COUNTY OFFICIAL)

(DEPUTY)

FILED Jan. 4, 1991
BAKER COUNTY SURVEYOR
SURVEY NO. 11-41-10