



BASIS OF BEARING

The South line of the Southwest quarter of Section 3, Township 11 South, Range 41 East of the Willamette Meridian being North 89°29' West, as per BLM survey by C. Albert White, under BLM Special Instructions dated Sept. 3, 1940.

SCALE: 1" = 500'

LEGEND

- Found 2 1/2" iron pipe with 3" brass cap, set by C. Albert White under BLM Special Instructions dated Sept. 3, 1940.
- ⊙ Set 5/8" x 30" iron pin with 2 1/2" aluminum cap, marked as per Baker County monumentation records, filed separately
- { } Record measurement as per survey by C. Albert White, under BLM Special Instructions dated September 3, 1940

REFERENCE MATERIAL

- Field notes of GLO Contract No. 211, executed by Benjamin Vaughn, dated July 14, 1874
- Field notes of BLM dependent resurvey, executed by C. Albert White, under special instructions dated September 3, 1940, included under Group No. 261
- Microfilm Document Number B0013 0007

NARRATIVE

This survey was performed at the request of Patrick Marolla, on behalf of Hancock Forest Management, land manager of lands shown. Mr. Marolla wanted a portion the exterior of their ownership within Section 11 surveyed, monumented and marked with flagging and paint on adjacent trees. I recover the monuments set by BLM dependent resurvey performed by C. Albert White as shown hereon. I break the section as per BLM Manual of Instructions 2009. I find no other unusual conditions with this survey.

NOTE:
For monumentation information, see monumentation record, filed separately

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JUNE 2, 2010
JEFFREY S. HSU
83571

Renewal Date: June 30, 2015

BAGETT, GRIFFITH & BLACKMAN
2006 Adams Avenue, LaGrande, Oregon
Map of Survey

Situated in Section 11, Township 11 South, Range 41 East of the Willamette Meridian

BAKER COUNTY, OREGON

SURVEYED FOR	Hancock Forest Management
SURVEYED BY	J. S. H.
Scale: 1" = 500'	Drawn by: J. S. H. July/Aug 2014

FILED Aug. 11, 2014
BAKER COUNTY SURVEYOR
SURVEY NO. 11-41-60