


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

**DIAGRAM**



V-11

**HISTORY OF ORIGINAL CORNER ESTABLISHMENT:**

THIS CORNER WAS ORIGINALLY ESTABLISHED BY BENJ. F. VAUGHAN UNDER GENERAL LAND OFFICE CONTRACT NO. 211, DATED JULY 14, 1874. SURVEYOR GENERAL LAND OFFICE NOTES STATE, "SET STONE 12"X10"X8" FOR THE 1/4 SECTION CORNER".

THOMAS HANLEY RE-ESTABLISHED THIS CORNER WITH A 12" BRIDGE SPIKE, AT THE INTERSECTION OF AN EAST-WEST FENCE WITH AN OLD FENCE REMNANT, PER PARTITION PLAT NO. P2007-020, SURVEY NO. 11-43-16MP, FILED OCTOBER 30, 2007.

**DESCRIPTION OF CORNER EVIDENCE FOUND:**

FOUND A 12" BRIDGE SPIKE, AT INTERSECTION OF EAST/WEST FENCE AND REMNANT NORTH FENCE.


**DESCRIPTION OF MONUMENT AND ACCESSORIES I ESTABLISHED TO PERPETUATE THE ORIGINAL LOCATION OF THIS CORNER:**

RE-ESTABLISHED THE CORNER BY REPLACING EXISTING 12" BRIDGE SPIKE IN THE SAME POSITION AS IT WAS RECOVERED.

SET 3-1/4" ALUMINUM CAP ON A 5/8" X 30" IRON ROD, UP 2" ABOVE THE GROUND, NEXT TO A RAILROAD TIE FENCE POST LYING ON SOUTHERLY SIDE OF MONUMENT. THE CAP IS MARKED AS SHOWN BELOW.

**THE REFERENCES SET FOR SAID CORNER ARE AS FOLLOWS:**

- 1) A 5/8" X 30" IRON ROD WITH A RED PLASTIC CAP, DOWN 1", STAMPED "ODOT CONTROL" BEARS S75°01'36"W, 4.18 FEET.
- 2) A 5/8" X 30" IRON ROD WITH A RED PLASTIC CAP, FLUSH, STAMPED "ODOT CONTROL" BEARS N47°46'52"W, 12.11 FEET.
- 3) A 5/8" X 30" IRON ROD WITH A RED PLASTIC CAP, FLUSH, STAMPED "ODOT CONTROL" BEARS N63°13'09"E, 11.07 FEET.
- 4) A 5/8" X 30" IRON ROD WITH A RED PLASTIC CAP, DOWN 1", STAMPED "ODOT CONTROL" BEARS S56°22'08"E, 13.24 FEET.



WITNESSES:  
MARK STEWART, CHASE KING

I HEREBY CERTIFY THAT THE ABOVE CORNER POSITION WAS RE-ESTABLISHED AS HEREON DESCRIBED ON AUGUST 30, 2017.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Bret N. Elithorp*

OREGON  
JAN 14, 2003  
BRET N. ELITHORP  
61348

RENEWS: 12/31/2019

OREGON DEPARTMENT OF TRANSPORTATION  
**RIGHT OF WAY  
ENGINEERING**

FILED February 19, 2018

BAKER COUNTY SURVEYOR

SURVEY NO. 11-43-21

Section	DURKEE STOCK PILE SITE		
Highway	OLD HIGHWAY 30 (COUNTY ROAD S39)		
County	BAKER	Scale	NTS
Purpose	ODOT BOUNDARY	Date	FEB. 15, 2017