

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established by Herman D. Gradon under GLO contract no. 428 dated Dec. 16, 1881.

Surveyor General records state:

Set a granite stone 17 x 8 x 3 inches, 10 inches in the ground for 1/4 sec cor marked 1/4 on N face and raised mound of stone alongside.

DIAGRAM

T 11 S R 44 E

$\frac{1}{4}$ $\frac{S 21}{S 28}$

Description of corner evidence found:

Found a granite stone 13 x 9 x 5 inches in place in old fence corner.

Description of monument and accessories established to perpetuate the original location of this corner:

Set a 2½ inch brass cap on a 1 inch iron pipe, 31 inches long, and projecting 6 inches out of the ground. Buried original stone 1 foot south of brass cap.

Brass cap marked thus: T 11 S R 44 E

$\frac{1}{4}$ $\frac{S 21}{S 28}$

CS 1981

I hereby certify that the above described corner monument was properly established under my direct supervision on Sept. 4, 1981, and witnessed by Brad Gordon, Tom Fisk, Jim DeMastus and Dick D'Ewart

REGISTERED
PROFESSIONAL
LAND SURVEYOR

James D. Hanley
OREGON
SEPTEMBER 23, 1977
JAMES D. HANLEY
1206