


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established by Herman D. Gradon under GLO contract no. 428 dated Dec. 16, 1881.

Surveyor General records state:

Set a granite stone 12 x 12 x 5 ins 8 ins in the ground for 1/4 sec cor marked 1/4 on the north side, dug pits 18 x 18 x 12 ins east and west of stone 5 1/2 feet distance and raised mound of earth 1 1/2 feet high and 3 1/2 feet base.



Description of corner evidence found:

Found a granite stone 15 x 14 x 5 inches and marked 1/4 on the north side.

The found stone was laid over in an old fence corner from which the fence runs north, south and east.

Description of monument and accessories established to perpetuate the original location of this corner:

Set a 2 1/2 inch brass cap on a 1 inch iron pipe 31 inches long and projecting 6 inches out of the ground with a surrounding rock mound. Buried original stone 1 foot north of brass cap.

Brass cap marked thus: T 11 S R 44 E

1	S 22
4	S 27

CS 1981

I hereby certify that the above described corner monument was properly established under my direct supervision on Sept. 4, 1981, and witnessed by Brad Gordon, Tom Fisk, Jim DeMastus and Dick D'Ewart

REGISTERED PROFESSIONAL LAND SURVEYOR

James D. Hanley

OREGON SEPTEMBER 23, 1977 JAMES D. HANLEY 1206

Office of..... County of.....
 State of..... I hereby certify that the within instrument was filed in this office
 for record on the..... day of....., 19.....
 by
 (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

FILED Oct 16, 1981
 BAKER COUNTY SURVEYOR
 SURVEY NO. 11-44-6