


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established by Herman D. Gradon under GLO contract no. 428 and dated Dec. 16, 1881.

Surveyor General records state:

Set a granite stone 20 x 9 x 8 ins 15 ins in the ground for 1/4 sec cor marked 1/4 on the west side, dug pits 18 x 18 x 12 ins north and south of stone 5 1/2 feet dist and raised mound of earth 1 1/2 feet high by 4 foot base.



Description of corner evidence found:

Found a stone 20 x 10 x 6 inches firmly set at the base of an old fence corner gate post and marked 1/4 on the east side.

Description of monument and accessories established to perpetuate the original location of this corner:

Set a 2 1/2 inch brass cap on a 1 inch iron pipe 31 inches long and projecting 6 inches out of the ground with a surrounding rock mound. Buried the original stone 1 foot north of the brass cap.

Brass cap marked thus:

T 11 S R 44 E

1/4

S 27 S 26

CS 1981

I hereby certify that the above described corner monument was properly established under my direct supervision on Sept. 11, 1981, and witnessed by Jim DeMastus and Dick DeWart.

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

James D. Hanley

OREGON
SEPTEMBER 23, 1977
JAMES D. HANLEY
1206

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....

..... by

(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

FILED Oct 16, 1981

BAKER COUNTY SURVEYOR

SURVEY NO. 11-44-8