


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established by Herman D. Gradon under GLO contract no. 428 dated Dec. 16, 1881.

Surveyor General records state:

Set a basalt stone 14 x 8 x 5 ins 9 ins in the ground for cor to secs 27, 28, 33 and 34 marked with 1 notch on S and 3 notches on E edges and raised mound of stone.




Description of corner evidence found:

Found a stone 18 x 10 x 5 ins firmly set in an old fence corner and marked with 1 notch on south and 3 notches on east edges. Fence line bears north, south and west from stone.

Description of monument and accessories established to perpetuate the original location of this corner:

Set a 2½ inch brass cap on a 1 inch iron pipe 31 inches long and projecting 6 inches out of the ground with a surrounding rock mound. Buried original stone 1 foot north of brass cap.

Brass cap marked thus:



I hereby certify that the above described corner monument was properly established under my direct supervision on Sept. 11, 1981, and witnessed by Jim DeMastus and Dick D'Ewart.

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

James D. Hanley

**OREGON
SEPTEMBER 23, 1977
JAMES D. HANLEY
1206**

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....

..... by

(COUNTY OFFICIAL)

(DEPUTY)

Form R6-7100-57 (9/71)

FILED Oct 16 1981
BAKER COUNTY SURVEYOR
SURVEY NO. 11-44-11