


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established by Herman D. Gradon under GLO contract no. 428 dated Dec. 16, 1881.

Surveyor General records state:

Set a basalt stone 13 x 10 x 3 ins 8 ins in the ground for 1/4 sec cor marked 1/4 on N face, dug pits 18 x 18 x 12 ins east and west of stone 5 1/2 feet dist and raised mound of earth 1 1/2 feet high and 3 1/2 feet base.



Description of corner evidence found:

Found a stone 13 x 10 x 3 ins firmly set and marked 1/4 on north face.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set a 2 1/2 inch brass cap on a 1 inch iron pipe 31 inches long and projecting 6 inches out of the ground with a surrounding rock mound. Buried original stone 1 foot north.

Brass cap marked thus: T 11 S R 44 E

1/4	S 27 S 34
-----	--------------

CS 1981

I hereby certify that the above corner monument was properly established under my direct supervision on Sept. 11, 1981, and witnessed by Jim DeMastus and Dick D'Ewart.

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

James D. Hanley
**OREGON
SEPTEMBER 23, 1977
JAMES D. HANLEY
1206**

Office of..... County of.....
 State of....., I hereby certify that the within instrument was filed in this office
 for record on the..... day of....., 19.....
 by
 (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

FILED Oct 16, 1981
 BAKER COUNTY SURVEYOR
 SURVEY NO. 11-44-12