

SEARCHING EASTERN PART OF THE SECTIONS
18 & 19 T. 11 S., R. 46 E. W.M., Ore.

FILED 11-14-1916
DAKER COUNTY SURVEYOR
SURVEY NO. 11-46-1

From the section corner common to Sections 18, 19, T. 11 S., R. 46 E. W.M. and 13 and 20, T. 11 S., R. 45 E. W.M. I run Easterly along a random line and find the quarter corner between Sections 18 and 19, and determine the true bearing of the line to be North $89^{\circ}41'$ East. I continue North $89^{\circ}41'$ East and intersect the center line of the Homestead Branch of the Oregon Short Line Railroad at Engineers Station 1081+21.3. I continue North $89^{\circ}41'$ East and intersect the left bank of the Snake River where I make diligent search over wide area. The meander corner between Sections 17 and 20 has been destroyed. I return to Railroad Station 1081+21.3 and run South $89^{\circ}41'$ West a distance of 127.5 feet and make diligent search over wide area. The section corner common to Sections 17, 18, 19, 20 has been destroyed. I set steel pin for temporary section corner common to Sections 17, 18, 19, 20.