

FED. Aug. 14, 1957.
BAKER CO., IDAHO
SURVEY LINE #62

RUNNING NORTHERLY BETWEEN SECTIONS 17 & 18
& SECTIONS 7 & 8, T. 11 S., R. 46 E., U.M., Ora.

From the temporary section corner common to Sections 17, 18, 19, 20, I run Northerly along a random line and find the $\frac{1}{2}$ corner between Sections 17 and 18. I continue Northerly 2640 feet and make diligent search and fail to find corner common to Sections 7, 8, 17, 18. I continue Northerly 2640 feet and make diligent search and fail to find $\frac{1}{2}$ corner common to Sections 7 and 8. I continue Northerly 2700 feet and find corner common to Sections 5, 6, 7, 8. I determine the true bearing between the corner common to Sections 5, 6, 7, 8 and the $\frac{1}{2}$ corner common to Sections 17 and 18 to be S. $0^{\circ}49' E.$. From the corner common to Sections 5, 6, 7, 8 which has been preserved by 1" pipe with 5 notches on East and 5 notches on South side, I run S. $0^{\circ}41' E.$, 2660.0 feet and set temporary $\frac{1}{2}$ corner. I continue S. $0^{\circ}41'E.$, 2660.0 feet and set temporary section corner for Sections 7, 8, 17, 18. I continue S. $0^{\circ}41' E.$, 2660.0 feet to the $\frac{1}{2}$ corner common to Sections 17 and 18. I return to the temporary section corner and run West 2640 feet and make diligent search over wide area and fail to find the $\frac{1}{2}$ corner between Sections 7 and 18. I return to the temporary corner of Sections 7, 8, 17, 18 and run East to the left bank of the Snake River. I make diligent search and fail to find meander corner between Sections 8 and 17. I return to temporary section corner and set at that point 12" x 12" x 13" basalt stone with 4 notches on South and 5 notches on East face, raised mound of stone along side and painted same with yellow paint, set 3/4" x 10' pipe with green and red flag on point of corner. I return to the temporary $\frac{1}{2}$ corner between Sections 7 and 8 and set at that point 8" x 10" x 11 $\frac{1}{4}$ " stone with $\frac{1}{4}$ on West face, raised mound of stone beside and painted same yellow set 3/4" x 10' pipe with green and orange flag on corner. I return to the $\frac{1}{2}$ corner between Sections 17 and 18 and run S. $0^{\circ}41' E.$, 2635.62 feet where I intersect the South line of Section 18. At this point I set 1 $\frac{1}{2}$ " pipe 3' long with brass cap stemmed $\frac{18}{17}$ for the corner common to Sections 17, 18, 19, 20. I continue S. $0^{\circ}49' E.$ to left bank of Snake River and make diligent search. I fail to find meander corner between Sections 19 and 20.