

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


P-13

History of original corner establishment:

Corner established by Henry W. Cooke under Contract No. 427 and dated December 15, 1881.

Surveyor General records state:

Set a basalt stone 18 x 16 x 14 ins 12 ins in ground for 1/4 sec cor marked 1/4 on W face from which:
A pine 18" dia bears N18°E, 15 lks dist marked 1/4S BT. A pine 12" dia bears S78°W, 32 lks dist marked 1/4S BT.



Description of corner evidence found:

Found a basalt stone 16 x 13 x 13" (record 18 x 16 x 14") firmly set and marked 1/4 on top from which:

A p pine 36" dia bears N20°E (record N18°E), 9.9' with scribing visible.

No evidence of other BT.

Description of monument and accessories established to perpetuate the original location of this corner:

At position of found stone...

Set 2 1/2" aluminum pipe with 2 1/2" aluminum cap 23" in the ground and surrounded with a mound of earth and stone. Cap marked as shown in corner diagram. Buried corner stone alongside.

New bearing tree established:

A p pine 31" dia bears S50°W, 47.4' marked 1/4S21 BT.

New bearing tree has a brass washer stamped PLS 1106 nailed to face of blaze. Attached signs 54-3 & 54-9 and painted face of blaze and a 6" band around each BT. Set steel fence post North of corner and attached sign 54-9.

Compass declination 19° East.

I hereby certify that the above corner monument was properly re-established to U.S.F.S. standards under my supervision and witnessed by Scott Munro on May 13, 1987.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of.....County Surveyor..... County of..... Baker.....
State of..... Oregon....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....

..... by
(COUNTY OFFICIAL) (DEPUTY)

FILED 6-3-87
BAKER COUNTY SURVEYOR
SURVEY NO. 12-36-9