

HORIZONTAL CONTROL DATA

OREGON STATE PLANE, NORTH ZONE (3601)

BAKER AND GRANT COUNTIES, OREGON

STA. NAME: K35

QUARTER SECTION: SE 1/4

GEODETIC COOR: NAD 83(91)

SEC. 28 TWP.11S RGE.35 1/2E
W.M., GRANT COUNTY, OREGON
DATE FOUND: 8/29/1991

LAT: 44°34'47.16304" N

LONG: 118°25'13.74099" W

SURVEYOR: LAYNE CASWELL, PLS737

SP. COOR: NAD 83(91)

FIRM: EAGLE GPS SURVEY CORP

N: 339866.375 Int.Ft.

13545 NW SCIENCE PARK DR

E: 8743866.129 Int.Ft.

PORTLAND, OR. 97229

THETA: 1°28'29.150"

(503) 643-1073

SCALE FACTOR: 0.999947052

SURVEY TYPE: GPS

ELEV: 4276.35 US.Ft.

ORDER: FIRST

ELEV. DATUM: NGVD 29

DIRECTIONS "TO REACH"

THE STATION WAS RECOVERED IN GOOD CONDITION.

THE STATION IS LOCATED 20.3 MILES EAST ALONG US HIGHWAY 26 FROM THE POST OFFICE IN PRAIRIE CITY ABOUT 0.05 MILE WEST OF MILE POST 195.

THE STATION IS A USC&GS BENCH MARK DISK SET INTO THE TOP OF A 25 CM SQUARE CONCRETE MONUMENT THAT PROJECTS 20 CM. IT IS 7.0 METERS (23.0 FEET) NORTH OF THE CENTERLINE OF THE ROAD, 5.6 METERS SOUTH OF THE SOUTH BANK OF A CREEK AND 0.35 METERS NORTH OF A WITNESS POST.

DESCRIBED BY L.L. RIGGERS.

FILED Feb. 24, 1992

BAKER COUNTY SURVEYOR

SURVEY NO. 12-37-66
12-36-64

SHEET 8/8