


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

None. Corner established with this survey.



Description of corner evidence found:

None.

There is a 1957 USFS location poster on a 30" douglas fir 20' NW of corner point.

Description of monument and accessories I established to perpetuate the original location of this corner:

At position established by survey...

Set 2½" aluminum pipe with 2½" aluminum cap 20" in the ground and surrounded with a mound of earth and stone. Cap marked as shown in corner diagram.

New bearing trees established:

A 9" douglas fir brs N54½°E, 39.4' dist mkd S1/16S6 BT.

A 8" juniper brs S04°W, 73.7' dist mkd S1/16S1 BT.

New bearing trees have a brass washer stamped PLS 1106 nailed to face of blaze. Attached signs 54-3 & 54-9, painted face of blaze and 6" band of red around each BT. Set steel fence post South of corner and attached sign 54-9.

Compass declination 19° East.

I hereby certify that the above corner monument was properly established to U.S.F.S. standards by me on November 17, 1987.

| |
|---|
| REGISTERED PROFESSIONAL LAND SURVEYOR |
|---|

William R. Wells

| |
|---|
| OREGON JULY 22, 1977 WILLIAM R. WELLS 1106 |
|---|

Office of.....County Surveyor..... County of... Baker.....
 State of.....Oregon....., I hereby certify that the within instrument was filed in this office
 for record on the..... day of....., 19.....

..... by
 (COUNTY OFFICIAL) (DEPUTY)