

HORIZONTAL CONTROL DATA

OREGON STATE PLANE, NORTH ZONE (3601)

BAKER AND GRANT COUNTIES, OREGON

STA. NAME: SQUAW AZ.MK.

QUARTER SECTION: NW 1/4

GEODETIC COOR: NAD 83(91)

SEC. 8 TWP.12S RGE.36E,W.M.
BAKER COUNTY,OREGON
DATE FOUND:8/29/1991

LAT: 44°32'30.02963" N

LONG: 118°19'38.61591" W

SURVEYOR: LAYNE CASWELL,PLS737

SP. COOR: NAD 83(91)

FIRM: EAGLE GPS SURVEY CORP

N: 326622.590 Int.Ft.

13545 NW SCIENCE PARK DR

E: 8768486.177 Int.Ft.

PORTLAND, OR. 97229

THETA: 1°32'26.816"

(503) 643-1073

SCALE FACTOR: 0.999954046

SURVEY TYPE: GPS

ELEV: 4842.24 US.Ft.

ORDER: FIRST

ELEV. DATUM: NGVD 29

DIRECTIONS "TO REACH"

THE STATION IS LOCATED 11.0 MILES NORTHWEST ALONG US HIGHWAY 26 FROM THE POST OFFICE IN UNITY AT MILEPOST 200.8

THE STATION IS A NGS AZIMUTH MARK DISK SET INTO A CONCRETE MONUMENT THAT IS FLUSH WITH THE GROUND. IT IS 10.7 METERS NE OF THE TOP EDGE OF A HIGHWAY CUT, 8.2 METERS (26.9 FEET) SW OF A RIGHT OF WAY FENCE, 6.6 METERS OF A JUNIPER TREE, 1.1 METER (3.6 FEET) WEST OF A CARIN, AND ABOUT 10 METERS HIGHER THAN THE HIGHWAY.

THE MARK CAN BE DRIVEN TO BY GOING TO THE EASTERLY END OF THE HIGHWAY CUT AND FOLLOWING THE TRACK ROAD NORTHWEST TO THE TOP OF THE CUT AND THE STATION.

DESCRIBED BY L.L. RIGGERS.

FILED Feb. 24, 1992

BAKER COUNTY SURVEYOR

SURVEY NO. 12-37-66
12-36-64

SHEET 5/8