

HORIZONTAL CONTROL DATA

OREGON STATE PLANE, NORTH ZONE (3601)

BAKER AND GRANT COUNTIES, OREGON

STA. NAME: K35 AZ.MK.

QUARTER SECTION: NE 1/4

SEC. 33 TWP.11S RGE.35 1/2E
W.M., GRANT COOUNTY, OREGON
DATE FOUND: 8/29/1991

SURVEYOR: LAYNE CASWELL, PLS737

FIRM: EAGLE GPS SURVEY CORP
13545 NW SCIENCE PARK DR

PORTLAND, OR. 97229

(503) 643-1073

SURVEY TYPE: GPS

ORDER: FIRST

GEODETIC COOR: NAD 83(91)

LAT: 44°34'37.35174" N

LONG: 118°24'51.31688" W

SP. COOR: NAD 83(91)

N: 338914.983 Int.Ft.

E: 8745514.207 Int.Ft.

THETA: 1°28'45.053"

SCALE FACTOR: 0.999947538

ELEV: 4295.95 US.Ft.

ELEV. DATUM: NGVD 29

DIRECTIONS "TO REACH"

THE STATION IS LOCATED ABOUT 20.7 MILES EAST ALONG HIGHWAY 26 FROM THE POST OFFICE IN PRAIRIE CITY AT MILE POST 195.35.

THE STATION IS AN ORHD BENCH MARK DISK SET INTO THE TOP OF A CONCRETE MONUMENT THAT IS FLUSH WITH THE GROUND. THE MARK IS 40.5 METERS (132.9 FEET) EAST OF THE CENTERLINE INTERSECTION OF A GRAVEL ROAD LEADING SOUTHWEST, 14.6 METERS NNE OF THE CENTERLINE OF THE HIGHWAY, 1.4 METERS SW OF A FENCE, 4.6 METERS (15.1 FEET) WEST OF A PINE TREE GROWING IN A DITCH AND 0.7 METER (2.3 FEET SW FROM A WITNESS POST.

DESCRIBED BY L.L. RIGGERS.

FILED Feb. 24, 1992

BAKER COUNTY SURVEYOR

SURVEY NO. 12-37-66
12-36-64

SHEET 6/8