

HORIZONTAL CONTROL DATA

OREGON STATE PLANE, NORTH ZONE (3601)

BAKER AND GRANT COUNTIES, OREGON

STA. NAME: SQUAW

QUARTER SECTION: NE 1/4

GEODETIC COOR: NAD 83(91)

SEC. 7 TWP.12S RGE.36E,W.M.
BAKER COUNTY, OREGON
DATE FOUND: 8/29/1991

LAT: 44°32'38.91709" N

LONG: 118°20'12.73836" W

SURVEYOR: LAYNE CASWELL, PLS737

SP. COOR: NAD 83(91)

FIRM: EAGLE GPS SURVEY CORP

N: 327455.965 Int.Ft.

13545 NW SCIENCE PARK DR

E: 8765991.693 Int.Ft.

PORTLAND, OR. 97229

THETA: 1°32' 2.617"

(503) 643-1073

SCALE FACTOR: 0.999953579

SURVEY TYPE: GPS

ELEV: 4906.43 US.Ft.

ORDER: FIRST

ELEV. DATUM: NGVD 29

DIRECTIONS "TO REACH"

THE STATION IS LOCATED 11.4 MILES NORTHWEST ALONG US HIGHWAY 26 FROM THE POST OFFICE IN UNITY AT MILEPOST 200.4

THE STATION IS 15.9 METERS (51.8 FEET) NORTHEAST OF BM T 703 1985, 15.2 METERS (49.9 FEET) SOUTHWEST OF THE CENTERLINE OF THE HIGHWAY, 33.8 METERS NNW OF THE CENTERLINE OF USFS ROAD 105 AND 1.4 METERS NE OF THE TOP NORTH SIDE OF A CUT ON THE OLD HIGHWAY.

DESCRIBED BY L.L. RIGGERS.

FILED Feb. 24, 1992

BAKER COUNTY SURVEYOR

SURVEY NO. 12-37-66
12-36-64

SHEET 7/8