


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

HISTORY OF ORIGINAL CORNER ESTABLISHMENT:

THIS CORNER WAS ORIGINALLY ESTABLISHED BY W.R. GRADON UNDER CONTRACT NO. 409 DATED MAR. 28, 1882.

SURVEYOR GENERAL LAND OFFICE RECORDS STATE:
 "SET BASALT STONE 14"X12"X8", 10" IN GROUND FOR THE CORNER TO SECTIONS 19, 20, 29, & 30, MARKED WITH 2 NOTCHES ON THE SOUTH AND 5 NOTCHES ON THE EAST EDGES. DUG PITS 18"X18"X12" IN EACH SECTION 5-1/2 FT DISTANT AND RAISED A MOUND OF EARTH 2 FT HIGH, 4-1/2 FT BASE ALONGSIDE."

DIAGRAM



R-5

DESCRIPTION OF CORNER EVIDENCE FOUND:


FOUND A 14"X12"X6" BASALT STONE WITH 5 NOTCHES IN EAST FACE AND 2 NOTCHES IN THE SOUTH FACE, LYING ON ITS SIDE ON TOP OF THE GROUND

DESCRIPTION OF MONUMENT AND ACCESSORIES I ESTABLISHED TO PERPETUATE THE ORIGINAL LOCATION OF THIS CORNER:

RE-ESTABLISHED THE CORNER BY REPLACING EXISTING STONE IN THE SAME POSITION AS IT WAS RECOVERED.

SET 3-1/4" ALUMINUM CAP ON A 5/8" X 30" IRON ROD, FLUSH WITH GROUND, SURROUNDED BY MOUND OF STONES, WITH THE ORIGINAL STONE BURIED BESIDE, AND A POST WITH PADDLE SET ALONGSIDE.
 THE CAP IS MARKED AS SHOWN BELOW.

THE REFERENCES SET FOR SAID CORNER ARE AS FOLLOWS:
 1) A SILVER DEEPI MAGNET BURIED 6" BELOW THE GROUND BEARS S38°15'38"W, 19.58 FEET.
 2) A 5/8" X 30" IRON ROD WITH A 1-1/2" ALUMINUM CAP, UP 1", STAMPED "ODOT" BEARS N75°37'53"W, 21.33 FEET.
 3) A BLUE DEEPI MAGNET BURIED 7" BELOW THE GROUND BEARS N67°44'44"E, 21.38 FEET.
 4) A 5/8" X 30" IRON ROD WITH A 1-1/2" ALUMINUM CAP, UP 1", STAMPED "ODOT" BEARS S55°13'51"E, 31.23 FEET.



REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

Bret N. Elithorp

OREGON
 JAN 14, 2003
 BRET N. ELITHORP
 61348

WITNESSES:
 BRET ELITHORP, PLS
 MARK STEWART, CODY WHEELER

I HEREBY CERTIFY THAT THE ABOVE CORNER POSITION WAS RE-ESTABLISHED AS HEREON DESCRIBED ON OCTOBER 1, 2014.

FILED Dec. 19, 2014

BAKER COUNTY SURVEYOR

SURVEY NO. 12-37-92

RENEWS: 12/31/2015

OREGON DEPARTMENT OF TRANSPORTATION



Section	CEMETERY QUARRY		
Highway	JOHN DAY HIGHWAY		
County	BAKER	Scale	NTS
Purpose	QUARRY BOUNDARY	Date	OCT. 20, 2014