


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

HISTORY OF ORIGINAL CORNER ESTABLISHMENT:

THIS CORNER WAS ORIGINALLY ESTABLISHED BY W.R. GRADON UNDER CONTRACT NO. 409 DATED MAR. 28, 1882.

SURVEYOR GENERAL LAND OFFICE RECORDS STATE:
 "SET BASALT STONE 15"X12"X7", 10" IN GROUND FOR COR TO SECS 21,22,27,& 28, MARKED WITH 2 NOTCHES ON S. AND 3 NOTCHES ON THE E. EDGES AND RAISED MOUND OF STONE 2 FT HIGH, 4.5 FT BASE ALONGSIDE."

DIAGRAM



R-13

DESCRIPTION OF CORNER EVIDENCE FOUND:

NONE

DESCRIPTION OF MONUMENT AND ACCESSORIES ESTABLISHED TO PERPETUATE THE ORIGINAL LOCATION OF THIS CORNER:


RE-ESTABLISHED THE CORNER BY DOUBLE PROPORTION BY HOLDING THE FOUND 3-1/4" ALUMINUM CAP AT THE NORTHWEST CORNER OF SECTION 29 AND THE 2-1/2" BRASS CAP AT THE NORTHEAST CORNER OF SECTION 27 IN THE EAST-WEST DIRECTION, AND THE FENCE LINE INTERSECTION AT THE NORTHWEST CORNER OF SECTION 16 AND THE REPLACED STONE AT THE EAST QUARTER CORNER OF SECTION 28 IN THE NORTH-SOUTH DIRECTION.

SET 3-1/4" ALUMINUM CAP ON A 5/8"X30" IRON ROD UP 4", WITH POST AND PADDLE 1 FOOT SOUTHWESTERLY.

THE CAP IS MARKED AS SHOWN BELOW.

THE REFERENCES SET FOR SAID CORNER ARE AS FOLLOWS:

- 1) A 5/8" X 30" SMOOTH IRON ROD WITH A 1-1/2" ALUMINUM CAP, FLUSH, STAMPED "ODOT" BEARS S79°50'17"E, 10.09 FEET.
- 2) A 5/8" X 30" SMOOTH IRON ROD WITH A 1-1/2" ALUMINUM CAP, FLUSH, STAMPED "ODOT" BEARS S09°45'51"E, 8.90 FEET.
- 3) A 5/8" X 30" SMOOTH IRON ROD WITH A 1-1/2" ALUMINUM CAP, FLUSH, STAMPED "ODOT" BEARS S63°38'12"W, 7.65 FEET.
- 4) A 5/8" X 30" SMOOTH IRON ROD WITH A 1-1/2" ALUMINUM CAP, FLUSH, STAMPED "ODOT" BEARS N13°45'52"E, 8.09 FEET.



WITNESSES:
 MARK STEWART, CHASE KING

I HEREBY CERTIFY THAT THE ABOVE CORNER POSITION WAS RE-ESTABLISHED AS HEREON DESCRIBED ON APRIL 3, 2017.

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

BEL

OREGON
 JAN 14, 2003
 BRET N. ELITHORP
 61348

RENEWS: 12/31/2017

OREGON DEPARTMENT OF TRANSPORTATION



**RIGHT OF WAY
 ENGINEERING**

FILED May 17, 2017

BAKER COUNTY SURVEYOR

SURVEY NO. 12-39-101

Section	UNITY RESEVOIR QUARRY		
Highway	DOOLEY MOUNTAIN HIGHWAY		
County	BAKER	Scale	NTS
Purpose	QUARRY BOUNDARY	Date	APRIL 11, 2017