


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

HISTORY OF ORIGINAL CORNER ESTABLISHMENT:

THIS CORNER WAS ORIGINALLY ESTABLISHED BY W.R. GRADON UNDER CONTRACT NO. 409 DATED MAR. 28, 1882.

SURVEYOR GENERAL LAND OFFICE RECORDS STATE:
 "SET BASALT STONE 14"X12"X10", 10" IN GROUND FOR 1/4 SEC COR MARKED 1/4 ON W.FACE AND RAISED MOUND OF STONE ALONGSIDE."

DIAGRAM



T-13

DESCRIPTION OF CORNER EVIDENCE FOUND:

FOUND 15"X11"X7" STONE MARKED WITH "1/4", WITH MOUND OF STONES 1 FT WESTERLY.

DESCRIPTION OF MONUMENT AND ACCESSORIES I ESTABLISHED TO PERPETUATE THE ORIGINAL LOCATION OF THIS CORNER:


RE-ESTABLISHED THE CORNER BY REPLACING EXISTING STONE IN THE SAME POSITION AS IT WAS RECOVERED.

SET 3-1/4" BRASS CAP ON A 5/8"X30" IRON ROD, UP 6", SURROUNDED BY MOUND OF STONES, WITH THE ORIGINAL STONE BURIED ALONGSIDE, AND A POST WITH PADDLE SET NEARBY.

THE CAP IS MARKED AS SHOWN BELOW.

THE REFERENCES SET FOR SAID CORNER ARE AS FOLLOWS:

- 1) A 5/8" X 30" SMOOTH IRON ROD WITH A 1-1/2" ALUMINUM CAP, FLUSH, STAMPED "ODOT" BEARS N60°54'02"E, 11.02 FEET.
- 2) A 5/8" X 30" SMOOTH IRON ROD WITH A 1-1/2" ALUMINUM CAP, FLUSH, STAMPED "ODOT" BEARS S29°15'18"E, 14.31 FEET.
- 3) A 5/8" X 30" SMOOTH IRON ROD WITH A 1-1/2" ALUMINUM CAP, FLUSH, STAMPED "ODOT" BEARS S45°47'50"W, 11.30 FEET.
- 4) A 5/8" X 30" SMOOTH IRON ROD WITH A 1-1/2" ALUMINUM CAP, FLUSH, STAMPED "ODOT" BEARS N40°45'47"W, 11.01 FEET.



WITNESSES:
 MARK STEWART, CHASE KING

I HEREBY CERTIFY THAT THE ABOVE CORNER POSITION WAS RE-ESTABLISHED AS HEREON DESCRIBED ON MARCH 28, 2017.

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

BQ

OREGON
 JAN 14, 2003
 BRET N. ELITHORP
 61348

RENEWS: 12/31/2017

OREGON DEPARTMENT OF TRANSPORTATION



FILED May 17, 2017

BAKER COUNTY SURVEYOR

SURVEY NO. 12-37-105

Section	UNITY RESEVOIR QUARRY		
Highway	DOOLEY MOUNTAIN HIGHWAY		
County	BAKER	Scale	NTS
Purpose	QUARRY BOUNDARY	Date	APRIL 11, 2017