


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

HISTORY OF ORIGINAL CORNER ESTABLISHMENT:

THIS CORNER WAS ORIGINALLY ESTABLISHED BY W.R. GRADON UNDER CONTRACT NO. 409 DATED MAR. 28, 1882.

SURVEYOR GENERAL LAND OFFICE RECORDS STATE:
 "SET A POST 4 FT LONG, 4 INCHES SQUARE, WITH MARKED STONE, 12" IN GROUND FOR COR. TO SECTIONS 28,29,32,& 33 MARKED T12S S28 ON NE, R37E S33 ON SE., S32 ON SW AND S29 ON NW FACES, WITH 1 NOTCH ON S., AND 4 NOTCHES ON E. EDGES. DUG PITS 18"X18"X12" IN EACH SEC., 5.5 FT. DIST. AND RAISED A MOUND OF EARTH 2 FT., 4.5 FT. BASE AROUND POST"

DIAGRAM



DESCRIPTION OF CORNER EVIDENCE FOUND:

HELD CENTER OF ROUSE LANE IN NORTH-SOUTH DIRECTION AS BEST EVIDENCE OF SOUTH LINE OF SECTION 29

DESCRIPTION OF MONUMENT AND ACCESSORIES I ESTABLISHED TO PERPETUATE THE ORIGINAL LOCATION OF THIS CORNER:


RE-ESTABLISHED THE CORNER BY HOLDING THE CENTER OF ROUSE LANE IN THE NORTH-SOUTH DIRECTION AND USED PROPORTIONING BETWEEN THE REMONUMENTED INTERSECTION OF THE CENTER OF ROUSE LANE WITH A NORTH-SOUTH FENCE LINE AT THE NORTH QUARTER CORNER OF SECTION 32 AND A FENCE CORNER FOUND AT THE SOUTHWEST CORNER OF SECTION 27 IN THE EAST-WEST DIRECTION.

SET 3-1/4" ALUMINUM CAP ON A 5/8"X30" IRON ROD, 4" BELOW THE GRAVEL SURFACE, IN ROUSE LANE.

THE CAP IS MARKED AS SHOWN BELOW.

THE REFERENCES SET FOR SAID CORNER ARE AS FOLLOWS:

- 1) A 5/8" X 30" SMOOTH IRON ROD WITH A 1-1/2" ALUMINUM CAP, DOWN 2", STAMPED "ODOT" BEARS N33°01'20"E, 28.94 FEET.
- 2) A 5/8" X 30" SMOOTH IRON ROD WITH A 1-1/2" ALUMINUM CAP, DOWN 2", STAMPED "ODOT" BEARS S29°39'14"E, 28.57 FEET.
- 3) A 5/8" X 30" SMOOTH IRON ROD WITH A 1-1/2" ALUMINUM CAP, DOWN 2", STAMPED "ODOT" BEARS S41°49'53"W, 33.77 FEET.
- 4) A 5/8" X 30" SMOOTH IRON ROD WITH A 1-1/2" ALUMINUM CAP, DOWN 2", STAMPED "ODOT" BEARS N39°26'48"W, 31.99 FEET.



WITNESSES:
 MARK STEWART, CHASE KING

I HEREBY CERTIFY THAT THE ABOVE CORNER POSITION WAS RE-ESTABLISHED AS HEREON DESCRIBED ON MARCH 27, 2017.

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

Bret N. Elithorp

OREGON
 JAN 14, 2003
 BRET N. ELITHORP
 61348

RENEWS: 12/31/2017

OREGON DEPARTMENT OF TRANSPORTATION



FILED May 17, 2017

BAKER COUNTY SURVEYOR

SURVEY NO. 12-37-108

Section	UNITY RESEVOIR QUARRY		
Highway	DOOLEY MOUNTAIN HIGHWAY		
County	BAKER	Scale	NTS
Purpose	QUARRY BOUNDARY	Date	APRIL 11, 2017