


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

HISTORY OF ORIGINAL CORNER ESTABLISHMENT:

THIS CORNER WAS ORIGINALLY ESTABLISHED BY W.R. GRADON UNDER CONTRACT NO. 409 DATED MAR. 28, 1882.

SURVEYOR GENERAL LAND OFFICE RECORDS STATE:
 "SET BASALT STONE 16"X16"X4", 11" IN GROUND FOR THE CORNER TO SECTIONS 9, 10, 15, & 16, MARKED WITH 4 NOTCHES ON THE SOUTH AND 3 NOTCHES ON THE EAST EDGES. DUG PITS 18"X18"X12" IN EACH SECTION 5-1/2 FT DISTANT AND RAISED A MOUND OF EARTH 2 FT HIGH, 4-1/2 FT BASE ALONGSIDE."

DIAGRAM



J-13

DESCRIPTION OF CORNER EVIDENCE FOUND:

NO MONUMENT FOUND.
 HELD BEST FIT INTERSECTION OF BARBED WIRE FENCE RUNNING EAST, WEST, AND SOUTH.


DESCRIPTION OF MONUMENT AND ACCESSORIES ESTABLISHED TO PERPETUATE THE ORIGINAL LOCATION OF THIS CORNER:

RE-ESTABLISHED THE CORNER BY HOLDING BEST FIT OF FENCE LINE INTERSECTIONS.

SET 3-1/4" ALUMINUM CAP ON A 5/8" X 30" IRON ROD, 3" BELOW GROUND, THE CAP IS MARKED AS SHOWN BELOW.

THE REFERENCES SET FOR SAID CORNER ARE AS FOLLOWS:

- 1) A 1/2" X 30" SQUARE IRON ROD WITH A 1-1/2" ALUMINUM CAP, STAMPED "ODOT", FLUSH, BEARS N13°55'44"W, 15.12 FEET.
- 2) A 1/2" X 30" SQUARE IRON ROD WITH A 1-1/2" ALUMINUM CAP, DOWN 1", STAMPED "ODOT" BEARS S85°35'28"E, 16.24 FEET.
- 3) A 1/2" X 30" SQUARE IRON ROD WITH A 1-1/2" ALUMINUM CAP, FLUSH, STAMPED "ODOT" BEARS S3°29'22"E, 14.83 FEET.
- 4) A 1/2" X 30" SQUARE IRON ROD WITH A 1-1/2" ALUMINUM CAP, DOWN 1", STAMPED "ODOT" BEARS S80°46'35"W, 12.59 FEET.



WITNESSES:
 MARK STEWART, CHASE KING


I HEREBY CERTIFY THAT THE ABOVE CORNER POSITION WAS RE-ESTABLISHED AS HEREON DESCRIBED ON MARCH 29, 2017.

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

BQ

OREGON
 JAN 14, 2003
 BRET N. ELITHORP
 61348

RENEWS: 12/31/2017

OREGON DEPARTMENT OF TRANSPORTATION
 **RIGHT OF WAY
 ENGINEERING**

Section	UNITY RESEVOIR QUARRY		
Highway	DOOLEY MOUNTAIN HIGHWAY		
County	BAKER	Scale	NTS
Purpose	QUARRY BOUNDARY	Date	APRIL 10, 2017

FILED *May 17, 2017*
 BAKER COUNTY SURVEYOR
 SURVEY NO. *12-37-99*