

MONUMENTATION AND MAINTENANCE

See standard U.S.F.S. "INDEX No." in the circle on the map. Monuments are stamped as shown below. On each Bearing tree, nailed a brass washer stamped "PLS 848" blaze above the BT scribe and nailed warning signs on the back. Set steel posts with warning and boundary signs, on line within 5 ft. of property corners, or a single post with a warning sign within 5 ft. of controlling corners.

See "CERTIFIED RECORD OF LAND CORNER MONUMENTATION" forms on file in the office of the Baker County Surveyor for a complete history, description of evidence found, monument set, and accessories established at all corners set or maintained.

- (A-15) T12S R39E S 34  
1/4 ---  
S 3  
T12S  
1972  
(BLM CAP)  
A Ponderosa Pine, 14' dia., bears N29°45'E, 21.5 ft., scribed: 1/4 S34 BT  
A Ponderosa Pine, 14' dia., bears S75°15'W, 31.8 ft., scribed: 1/4 S 3 BT
- (E-13) T12S R39E S 4 | S 3  
---  
S 9 | S10  
1991  
PLS 848  
Ponderosa Pine, 14' dia., bears N34°15'W, 58.9 ft., scribed: T12S R39E S 4 BT  
Juniper, 10' dia., bears N48°45'E, 20.0 ft., scribed: T12S R39E S 3 BT  
Ponderosa Pine, 12' dia., bears S63°00'E, 112.2 ft., scribed: T12S R39E S10 BT  
Juniper, 10' dia., bears S51°30'W, 21.9 ft., scribed: T12S R39E S 9 BT
- (E-15) T12S R39E S 3  
1/4 ---  
S10  
1972  
(BLM CAP)  
A Ponderosa Pine 12' dia., bears N64°30'E, 12.1 ft., scribed: 1/4 S 3 BT  
A Ponderosa Pine 14' dia., bears S66°30'W, 38.8 ft., scribed: 1/4 S10 BT
- (E-19) T12S R39E S 2  
1/4 ---  
S10  
1991  
PLS 848  
A Ponderosa Pine, 14' dia., bears N25°53'W, 13.2 ft., scribed: 1/4 S 2 BT  
A Ponderosa Pine, 10' dia., bears N35°18'E, 20.0 ft., scribed: 1/4 S 2 BT  
A Ponderosa Pine, 20' dia., bears S67°03'E, 15.1 ft., scribed: 1/4 S11 BT  
A Ponderosa Pine, 8' dia., bears S45°53'W, 8.0 ft., scribed: 1/4 S11 BT
- (F-16) T12S R39E NE 1/16  
S10  
1991  
PLS 848  
Ponderosa Pine, 16' dia., bears S87°26'W, 18.3 ft., scribed: NE 1/16 S10 BT  
Ponderosa Pine, 14' dia., bears N74°22'E, 34.5 ft., scribed: NE 1/16 S10 BT
- (F-17) T12S R39E N1/16  
S10 | S11  
1991  
PLS 848  
Ponderosa Pine, 12' dia., bears S47°45'E, 29.9 ft., scribed: N1/16 S11 BT  
Ponderosa Pine, 12' dia., bears S 6°33'W, 24.0 ft., scribed: N1/16 S10 BT
- (G-13) T12S R39E 1/4  
S 9 | S10  
1991  
PLS 848  
A 5/8" x 30' rebar, set 28" in the ground, with yellow plastic cap marked PLS 848 bears:  
No grooves on rebar: N59°30'W, 8.20 ft.  
1 groove on rebar: N51°45'E, 8.10 ft.  
2 grooves on rebar: S42°15'E, 7.70 ft.  
3 grooves on rebar: S50°45'W, 8.00 ft.
- (G-15) T12S R39E C1/4  
S10  
1991  
PLS 848  
Ponderosa Pine, 8' dia., bears N32°05'E, 12.0 ft., scribed: C1/4 S10 BT  
Ponderosa Pine, 8' dia., bears N61°52'E, 10.0 ft., scribed: C1/4 S10 BT  
Ponderosa Pine, 10' dia., bears S75°39'W, 12.2 ft., scribed: C1/4 S10 BT  
Ponderosa Pine, 12' dia., bears N14°23'W, 58.6 ft., scribed: C1/4 S10 BT
- (G-16) T12S R39E E 1/16  
C --- C  
S10  
1991  
PLS 848  
Ponderosa Pine, 12' dia., bears N31°54'E, 1.3 ft., scribed: C-E1/16 S10 BT  
Ponderosa Pine, 12' dia., bears S46°49'E, 60.7 ft., scribed: C-E1/16 S10 BT
- (G-17) T12S R39E 1/4  
S10 | S11  
1972  
(BLM CAP)  
A 5/8" x 30' rebar, set 28" in the ground, with yellow plastic cap marked PLS 848 bears:  
No grooves on rebar: N45°W, 8.50 ft.  
1 groove on rebar: N45°E, 7.90 ft.  
2 grooves on rebar: S45°W, 7.70 ft.
- (G-19) T12S R39E C1/4  
S11  
1991  
PLS 848  
Ponderosa Pine, 10' dia., bears S55°44'W, 93.8 ft., scribed: C1/4 S11 BT  
Ponderosa Pine, 10' dia., bears S87°39'W, 77.1 ft., scribed: C1/4 S11 BT  
A 5/8" x 30' rebar, driven 28" in the ground, with a yellow plastic cap marked PLS 848 bears:  
No grooves on rebar: N36°43'E, 11.1 ft.  
1 groove on rebar: S42°03'E, 11.3 ft.
- (H-20) T12S R39E SE 1/16  
S11  
1991  
PLS 848  
Ponderosa Pine, 20' dia., bears N12°57'W, 46.5 ft., scribed: SE 1/16 S11 BT  
Juniper, 10' dia., bears S 0°50'W, 81.2 ft., scribed: SE 1/16 S11 BT
- (J-13) T12S R39E S 9 | S10  
---  
S16 | S15  
1991  
PLS 848  
5/8" x 30' rebar, set 28" in the ground, with yellow plastic caps marked PLS 848 bears:  
No grooves on rebar: N45°W, 10.6 ft.  
1 groove on rebar: N45°E, 9.9 ft.  
2 grooves on rebar: S45°E, 10.1 ft.  
3 grooves on rebar: S45°W, 10.8 ft.
- (J-15) T12S R39E S10  
1/4 ---  
S15  
1986  
DRLS 1639  
Set 5/8" x 30' rebar, 28" in the ground, with yellow plastic cap marked PLS 848  
No grooves on rebar: NORTH 11.0 ft.  
1 groove on rebar: SOUTH 5.8 ft.
- (J-19) T12S R39E S 11  
1/4 ---  
S 14  
1972  
(BLM CAP)  
Set a 5/8" x 30' rebar, 28 ins. in the ground, with a yellow plastic cap marked PLS 848 which bears:  
No grooves on rebar: N5°45'E, 8.6 ft.  
1 groove on rebar: S1°15'E, 7.5 ft.

- (J-20) T12S R39E S 11  
E1/16 ---  
S 14  
1991  
PLS 848  
Doug Fir, 16' dia., bears N19°03'E, 14.8 ft., scribed: E1/16 S11 BT  
Doug Fir, 16' dia., bears S33°21'E, 12.3 ft., scribed: E1/16 S14 BT
- (J-21) T12S R39E S11 | S12  
---  
S14 | S13  
1991  
PLS 848  
Ponderosa Pine, 14' dia., bears N43°30'W, 44.6 ft., scribed: T12S R39E S11 BT  
Juniper, 10' dia., bears N00°15'E, 29.0 ft., scribed: T12S R39E S12 BT  
Juniper, 14' dia., bears S02°15'E, 32.2 ft., scribed: T12S R39E S13 BT  
Ponderosa Pine, 12' dia., bears S81°15'W, 54.7 ft., scribed: T12S R39E S14 BT
- (J-22) T12S R39E S 12  
W1/16 ---  
S 13  
1991  
PLS 848  
Juniper, 10' dia., bears N79°05'E, 15.8 ft., scribed: W1/16 S12 BT  
Ponderosa Pine, 16' dia., bears S42°07'W, 18.0 ft., scribed: W1/16 S13 BT
- (J-23) T12S R39E S 12  
1/4 ---  
S 13  
(BLM CAP)  
Ponderosa Pine, 10' dia., bears N45°15'E, 49.2 ft., scribed: 1/4 S12 BT  
1972
- (J-25) T 12 S  
S 12 | T 12 S  
R 40 E | A Red Fir, 14' dia., bears S17°15'W, 2.5 ft., scribed: T12S R39E S13 BT  
S 13 | S 18  
R 39 E | A Red Fir, 12' dia., bears N76°15'W, 8.3 ft., scribed: T12S R39E S12 BT  
1972  
(BLM CAP)
- (J5-21) T12S R39E W C  
1991  
PLS 848  
The following accessories are from the Line Tree:  
Witness corner bears N0°33'36"E, 10.0 ft., marked as shown in diagram.  
Ponderosa Pine, 12' dia., bears N45°15'W, 65.4 ft., scribed: LT S14 BT  
Juniper, 8' dia., bears N16°15'E, 22.6 ft., scribed: LT S13 BT
- (L-21) T12S R39E 1/4  
S14 | S13  
1972  
(BLM CAP)  
Ponderosa Pine, 16' dia., bears S68°45'W, 108.9 ft., scribed: 1/4 S14 BT  
Juniper, 18' dia., bears N74°30'E, 76.5 ft., scribed: 1/4 S13 BT
- (L-23) T12S R39E C 1/4  
S 13  
1991  
PLS 848  
Ponderosa Pine, 12' dia., bears N83°09'W, 73.8 ft., scribed: C1/4 S13 BT  
Ponderosa Pine, 16' dia., bears N 7°29'E, 64.9 ft., scribed: C1/4 S13 BT  
Ponderosa Pine, 16' dia., bears S88°05'E, 44.2 ft., scribed: C1/4 S13 BT  
Ponderosa Pine, 22' dia., bears S15°39'E, 23.6 ft., scribed: C1/4 S13 BT
- (L-24) T12S R39E E 1/16  
C --- C  
S 13  
1991  
PLS 848  
Juniper, 10' dia., bears N23°37'W, 75.2 ft., scribed: C-E1/16 S13 BT  
Ponderosa pine, 22' dia., bears S68°38'E, 130.7 ft., scribed: C-E1/16 S13 BT
- (L-25) T12S R39E R40E  
1/4 S13  
1991  
PLS 848  
Ponderosa Pine, 10' dia., bears S85°48'W, 44.9 ft., scribed: 1/4 S13 BT  
Ponderosa Pine, 12' dia., bears S69°41'W, 36.2 ft., scribed: 1/4 S13 BT  
Ponderosa Pine, 12' dia., bears S53°58'W, 30.3 ft., scribed: 1/4 S13 BT  
Ponderosa Pine, 6' dia., bears S24°25'W, 59.7 ft., scribed: 1/4 S13 BT
- (N-21) T12S R39E S14 | S13  
---  
S23 | S24  
1972  
(BLM CAP)  
Set a 5/8" x 30' rebar, 28 ins. in the ground, with a yellow plastic cap marked PLS 848 which bears:  
No grooves on the rebar: N52°15'E, 7.7 ft.  
1 groove on the rebar: S30°30'E, 7.7 ft.
- (N-23) T12S R39E S13  
1/4 ---  
S24  
1991  
PLS 848  
Set a 5/8" x 30' rebar, 28 ins. in the ground, with a yellow plastic cap marked PLS 848 which bears:  
No grooves on the rebar: N72°30'W, 9.4 ft.  
1 groove on the rebar: N34°45'E, 8.9 ft.  
2 grooves on the rebar: S70°15'E, 10.3 ft.  
Juniper, 8' dia., bears S50°15'W, 132.2 ft., scribed: 1/4 S24 BT
- (N-24) T12S R39E S 13  
E1/16 ---  
S 24  
1991  
PLS 848  
Ponderosa Pine, 28' dia., bears N35°25'W, 125.4 ft., scribed: E1/16 S13 BT  
Ponderosa Pine, 24' dia., bears S54°48'E, 61.9 ft., scribed: E1/16 S24 BT
- (N-25) T 12 S  
S 13 | T 12 S  
R 40 E | Juniper, 12' dia., bears N31°30'W, 116.7 ft., scribed: T12S R39E S13 BT  
S 24 | S 19  
R 39 E | Juniper, 10' dia., bears S58°30'W, 49.8 ft., scribed: T12S R39E S24 BT  
1972  
(BLM CAP)

