
CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of Original Corner Establishment:

This quarter corner was established by Reuben R. Leigh, Deputy Surveyor under Contract No. 462 and being dated April 11, 1883. His notes states he set a Basalt stone 12" x 12" x 8" buried 8 inches in the ground for the 1/4 corner common to Sections 14 & 15, T 12 S, R 39 E W.M., marked 1/4 on the West face and raised a mound of stone alongside.

Description of Corner Evidence Found:

At the location of this one quarter corner I found a Basalt stone measuring 12" x 11" x 8" as shown in the accompanying photo, of which fits the description of the stone Reuben R. Leigh said he had set. I could not identify any visible markings on the stone. I accepted its location as the 1/4 corner as this was the only stone in the area and there was no other evidence available.



To perpetuate this 1/4 corner, at the exact location of the stone, I set a 2 inch Brass Cap on a 1" x 30" galvanized iron pipe. I buried the pipe to within 8 inches above the ground surface. The original stone was turned upside down and buried on the West side of the new monument with the face of the stone where the marks should have appeared facing the pipe. I then placed a mound of stone and soil three feet in diameter about the monument. The brass cap monument is stamped as shown in the accompanying photo.

I then set four bearing objects as follows:

Reference No. 1 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears North,15.00 feet distance. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 2 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears South, 15.00 feet distance and in direct line with bearing object No. 1. Monument pin was driven to within 6 inches above the ground surface.

Reference No.3 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears East, 15.00 feet distance. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 4 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears West, 15.00 feet distance and in direct line with bearing object No. 3. Monument pin was driven to within 6 inches above the ground surface.



Found a Basalt stone 12"x 11"x 8"as described in Reuben R. Leigh's field notes of his GLO survey.



Set brass cap monument to within 8" of the surface in a mound of stone 3 feet at base around monument. Original stone is buried on the West side of monument.



Brass Cap as stamped

This 1/4 corners handheld GPS geographic position. 44° 31' 21.180" N, 117° 54' 40.800" W NAD83

I, James H. Hambleton certify that this corner was properly reestablished as witnessed by John Eggers on July 25, 2012.

Dines House

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON JULY 10, 1964 JAMES H. HAMBLETON 645

Renews June 30, 2014

FILED Sept. 27, 2012
BAKER COUNTY SURVEYOR
SURVEY NO. (2-39-5)