
## CERTIFIED RECORD OF LAND CORNER MONUMENTATION

## **History of Original Corner Establishment:**

This quarter corner was established by Reuben R. Leigh, Deputy Surveyor under Contract No. 462 and being dated April 11, 1883. His notes states he set a Basalt stone 12" x 10" x 6" buried 8 inches in the ground for the 1/4 corner common to Sections 15 & 22, T 12 S, R 39 E W.M., marked 1/4 on the North face and raised a mound of stone alongside.

## **Description of Corner Evidence Found:**

At the location of this one quarter corner I found a Basalt stone measuring 12" x 10" x 6" as shown in the accompanying photo, of which fits the description of the stone Reuben R. Leigh said he had set. I found faintly visible markings of 1/4 on the top center face of the stone. The stone fits Reuben R. Leigh's description.



To perpetuate this 1/4 corner, at the exact location of the stone, I set a 2 inch Brass Cap on a 1" x 30" galvanized iron pipe. I buried the pipe to within 8 inches above the ground surface. The original stone was turned upside down and buried on the North side of the new monument with the face of the stone with the marks facing the pipe. I then placed a mound of stone and soil three feet in diameter about the monument. The brass cap monument is stamped as shown in the accompanying photo.

I then set four bearing objects as follows:

Reference No. 1 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears North,13.10 feet distance. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 2 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears South, 14.65 feet distance and in direct line with bearing object No. 1. Monument pin was driven to within 6 inches above the ground surface.

Reference No.3 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears East, 10.00 feet distance. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 4 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears West, 10.10 feet distance and in direct line with bearing object No. 3. Monument pin was driven to within 6 inches above the ground surface.



Found a Basalt stone 12"x 10"x 6"as described in Reuben R. Leigh's field notes of his GLO survey. The markings 1/4 are barely visible in the top center part of the stone.



Set brass cap monument to within 8" of the surface in a mound of stone 3 feet at base around monument. Original stone is buried on the North side of monument.



Brass Cap as stamped.

This 1/4 corners true geographic position. 44° 30' 56.52105" N, 117° 55' 15.99716" WNAD83

I, James H. Hambleton certify that this corner was properly reestablished as witnessed by John Eggers on July 25, 2012...

FILED Supt. 27, 2012
BAKER COUNTY SURVEYOR
SURVEY NO. 12-39-52

PROFESSIONAL'
LAND SURVEYOR

OREGON
JULY 10, 1964

JAMES H. HAMBLETON
645

Renews June 30, 2014