

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of Original Corner Establishment:

This quarter corner was established by Reuben R. Leigh, Deputy Surveyor under Contract No. 462 and being dated April 11, 1883. His notes states he set a Basalt stone 12" x 12" x 12" in the ground for the 1/4 corner common to Sections 23 & 24, T 12 S, R 39 E W.M., marked 1/4 on the West face and raised a mound of stone alongside.

Description of Corner Evidence Found:

At the location of this one quarter corner I found a small loosely placed mound of stones with a Basalt stone measuring 12" x 12" x 13" as shown in the accompanying photo, of which fits the description of the stone Reuben R. Leigh said he had set. I was unable to identify any marks on the stone. The large stone appears to have rolled out of place in the small mound of stone.



Found a Basalt stone 12" x 12" x 13" with a small mound of stone alongside as described by Reuben R. Leigh in his field notes.

Description of Monument and Accessories I Established to Perpetuate the Original Location of Corner:

To perpetuate this 1/4 corner, I set a 2 inch Brass Cap on a 1" x 30" galvanized iron pipe. I buried the pipe to within 8 inches above the ground surface. The original stone was turned upside down and buried on the West side of the new monument with the face of the stone where the marks should have appeared facing the pipe. I then placed a mound of stone and soil three feet in diameter about the monument. The brass cap monument is stamped as shown in the accompanying photo.



Set brass cap monument to within 8" of the surface in a mound of stone 3 feet at base around monument. Original stone is buried on the West side of monument.

I then set four bearing objects as follows:

Reference No. 1 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears North, 13.00 feet distance. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 2 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears South, 11.25 feet distance and in direct line with bearing object No. 1. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 3 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears East, 14.80 feet distance. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 4 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears West, 15.18 feet distance and in direct line with bearing object No. 3. Monument pin was driven to within 6 inches above the ground surface.



Brass Cap as stamped.

This Section corners true geographic position.
44° 30' 29.33209" N, 117° 53' 27.64082" W NAD83

I, James H. Hambleton certify that this corner was properly reestablished as witnessed by John Eggers on July 24, 2012.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JULY 10, 1964
JAMES H. HAMBLETON
645

FILED Sept. 27, 2012
DAKER COUNTY SURVEYOR
QUINCY NO. 12-39-54

Renews June 30, 2014