

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of Original Corner Establishment:

This section corner was established by Henry Meldrum, Deputy Surveyor under Contract No. 226 and being dated May 29, 1875. His notes states he set a Basalt stone 18" x 10" x 8" for the section corner common to Sections 23, 24, 25 & 26, T 12 S, R 39 E W.M.

This section corner was revisited by Reuben R. Leigh, Deputy Surveyor under Contract No. 462 and being dated April 11, 1883. His notes states he found a Basalt stone 18" x 10" x 8" marked with 2 notches on the South and 1 notch on the East edges. He repaired corner by raising a mound of stone alongside.

Description of Corner Evidence Found:

At this corner location I found a Basalt stone, measuring 18" x 10" x 8" and a raised mound of stone four feet to the West and alongside. The corner stone being firmly set in an upright position. The stone is dimly marked with two notches on the South face and one notch on the East face.



Found 18"x10"x8" basalt stone firmly in place as set by Henry Meldrum. Notice the mound of stone, as described by Reuben Leigh, four feet to the west of stone.



Set brass cap monument to within 8" of the surface in a mound of stone 3 feet at base around monument, original stone is buried on the North side of monument.

Description of Monument and Accessories I Established to Perpetuate the Original Location of Corner:

To perpetuate this section corner at the location of the stone, I set a 2 inch Brass Cap on a 1" x 30" galvanized iron pipe. I buried the pipe to within 8 inches above the ground surface. The original stone was turned upside down and buried on the North side of the new monument with the face of the stone where the marks appear facing the pipe. I then placed a mound of stone and soil three feet in diameter about the monument covering the brass cap. The brass cap monument is stamped as shown in the accompanying photo.



Brass Cap as stamped.

This Section corners true geographic position.
44° 30' 02.89886" N, 117° 53' 27.62307" W NAD 83

I then set four bearing objects as follows:

Reference No. 1 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears North, 13.40 feet distance. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 2 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears South, 13.00 feet distance and in direct line with bearing object No. 1. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 3 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears East, 14.10 feet distance. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 4 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears West, 12.95 feet distance and in direct line with bearing object No. 3. Monument pin was driven to within 6 inches above the ground surface.

I, James H. Hambleton certify that this corner was properly reestablished as witnessed by John Eggers on July 24, 2012.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

James H. Hambleton

OREGON
JULY 10, 1964
JAMES H. HAMBLETON
645

Renews June 30, 2014

FILED Sept. 27, 2012
BAKER COUNTY SURVEYOR
SURVEY NO. 12-39-55