
CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of Original Corner Establishment:

This 1/4 corner was established by Henry Meldrum, Deputy Surveyor under Contract No. 226 and being dated May 29, 1875. His notes states he set a Basalt stone 19" x 10" x 8" for the 1/4 corner common to Sections 28 & 33, T 12 S, R 39 E W.M.

Description of Corner Evidence Found:

At the location of this one quarter corner I found a Basalt stone measuring 17" x 10" x 8" as shown in the accompanying photo, It must be noted the dimensions of this stone does not fit the description of the stone Henry Meldrum said he had set. Meldrum seems to have possibly been guessing at some of the dimensions along this series of corners running along this East-West line. This stone being obviously set, though I found no visible markings on the stone. A small mound of stone was along-side. No other evidence is available thus I accepted its location as the 1/4 corner.



To perpetuate this 1/4 corner, at the location of the stone, I set a 2 inch Brass Cap on a 1" x 30" galvanized iron pipe. I buried the pipe to within 8 inches above the ground surface. The original stone was turned upside down and buried on the North side of the new monument. I then placed a mound of stone and soil three feet in diameter about the monument covering the brass cap. Also I placed a mound of small stones 3.5 feet East of the monument as shown in the accompanying photo. The brass cap monument is stamped as shown in the accompanying photo.

I then set four bearing objects as follows:

Reference No. 1 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears North, 12.00 feet distance. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 2 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears South, 12.00 feet distance and in direct line with bearing object No. 1. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 3 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears East, 12.00 feet distance. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 4 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears West, 12.00 feet distance and in direct line with bearing object No. 3. Monument pin was driven to within 6 inches above the ground surface.



Found an unmarked stone 17" x 10" x 8" and a small mound of stone at the corner location.



Set brass cap monument to within 8" of the surface in a mound of stone 3 feet at base around monument. Original stone is buried on the north side of monument. Note the mound of small stone I placed 3.5 feet East of the monument being residue from digging the monument hole.



Brass Cap as stamped.

This 1/4 corners handheld GPS geographic position. 44° 29' 13.080" N, 117° 56' 29.100" W NAD83

I, James H. Hambleton certify that this corner was properly reestablished as witnessed by John Eggers on July 27, 2012.

FILED Sept. 27 2012 BAKER COUNTY SURVEYOR SURVEY NO. 12-39-57 PROFESSIONAL'
LAND SURVEYOR

OREGON
JULY 10, 1964
JAMES H. HAMBLETON
645

REGISTERED

Renews June 30, 2014

V - 11 12