
CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of Original Corner Establishment:

This 1/4 corner was established by Henry Meldrum, Deputy Surveyor under Contract No. 226 and being dated May 29, 1875. His notes states he set a Basalt stone 20" x 9" x 6" for the 1/4 corner common to Sections 27 & 34, T 12 S, R 39 E W.M.

Description of Corner Evidence Found:

At the location of this one quarter corner I found a Basalt stone measuring 20" x 10" x 8" firmly planted in the ground and a small mound of stone alongside as shown in the accompanying photo, of which nearly fits the description of the stone Henry Meldrum said he had set. I could not identify any markings on the stone. This stone lies adjacent to an old historic fence corner. There is no other evidence available thus I accepted its location as the 1/4 corner. I can only assume Henry Meldrum possibly made an error in the dimensions of the stone as it does appear to be an original stone and was definitely protected during fence construction of the very old existing fence



To perpetuate this section corner, at the location of the stone, I set a 2 inch Brass Cap on a 1" x 30" galvanized iron pipe. I buried the pipe to within 8 inches above the ground surface. The original stone was turned upside down and buried on the North side of the new monument with the face of the stone where the marks would have appeared facing the pipe. I then placed a mound of stone and soil three feet in diameter about the monument covering the brass cap. The brass cap monument is stamped as shown in the accompanying photo.

I then set four bearing objects as follows:

Reference No. 1 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears North, 12.00 feet distance. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 2 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears South, 12.00 feet distance and in direct line with bearing object No. 1. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 3 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears East, 12.00 feet distance. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 4 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears West, 12.00 feet distance and in direct line with bearing object No. 3. Monument pin was driven to within 6 inches above the ground surface.



Found stone 20" x 10" x 8" firmly planted and small mound of stone, being located adjacent to an old historic fence corner where it appeared to have been protected from the long ago fence construction



Set brass cap monument to within 8" of the surface in a mound of stone 3 feet at base around monument. Original stone is buried on the North side of monument.



Brass Cap as stamped.

This 1/4 corners true geographic position. 44° 29'12.66916" N, 117° 55' 16.65598" W NAD83

I, James H. Hambleton certify that this corner was properly reestablished as witnessed by John Eggers on July 27, 2012.

Sept. 27, 2012

REGISTERED **PROFESSIONAL** LAND SURVEYOR

OREGON JAMES H. HAMBLETON 645

Renews June 30, 2014