

# CERTIFIED RECORD OF LAND CORNER MONUMENTATION

## History of Original Corner Establishment:

This 1/4 corner was established by Henry Meldrum, Deputy Surveyor under Contract No. 226 and being dated May 29, 1875. His notes states he set a Basalt stone 17" x 10" x 5" for the 1/4 corner common to Sections 26 & 35, T 12 S, R 39 E W.M.

## Description of Corner Evidence Found:

At the location of this one quarter corner I found a Basalt stone measuring 18" x 10" x 5" as shown in the accompanying photo, fitting the description of the stone Henry Meldrum said he had set. The stone had tipped over down the slope with the base very near its original location. I found no visible markings on the stone. A small mound of stone was alongside as shown in the accompanying photo. No other evidence is available thus I accepted its location as the 1/4 corner.



Found stone 18" x 10" x 5" with small mound of stone fitting the description given by Henry Meldrum, stone had tipped over and nearly buried

## Description of Monument and Accessories I Established to Perpetuate the Original Location of Corner:

To perpetuate this 1/4 corner, at the location of the stone, I set a 2 inch Brass Cap on a 1" x 30" galvanized iron pipe. I buried the pipe to within 8 inches above the ground surface. The original stone was turned upside down and buried on the North side of the new monument with the face of the stone where the marks would have appeared facing the pipe. I then placed a mound of stone and soil three feet in diameter about the monument covering the brass cap. The brass cap monument is stamped as shown in the accompanying photo.



Set brass cap monument to within 8" of the surface in a mound of stone 3 feet at base around monument, original stone is buried on the North side of monument.

I then set four bearing objects as follows:

Reference No. 1 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears North, 12.00 feet distance. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 2 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears South, 12.00 feet distance and in direct line with bearing object No. 1. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 3 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears East, 12.00 feet distance. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 4 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears West, 12.00 feet distance and in direct line with bearing object No. 3. Monument pin was driven to within 6 inches above the ground surface.



Brass Cap as stamped.

This 1/4 corners true geographic position.  
44°29'12.46686"N 117°54'04.37599"W NAD83

I, James H. Hambleton certify that this corner was properly reestablished as witnessed by John Eggers on July 26, 2012.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

OREGON  
JULY 10, 1964  
JAMES H. HAMBLETON  
645

Renews June 30, 2014

FILED Sept 27, 2012  
BAKER COUNTY SURVEYOR  
SURVEY NO. 12-39-61