

# CERTIFIED RECORD OF LAND CORNER MONUMENTATION

## History of Original Corner Establishment:

This Section corner was established by Henry Meldrum, Deputy Surveyor under Contract No. 226 and being dated May 29, 1875. His notes states he set a Basalt stone 14" x 12" x 5" for the section corner common to Sections 25, 26, 35 & 36, T 12 S, R 39 E W.M.

## Description of Corner Evidence Found:

At this corner location I found a Basalt stone, measuring 14" x 12" x 6" and a raised mound of stone alongside. The corner stone lying on its side as if it tipped over down the slope. The stone is dimly marked with one notch on the South face and no visible marks on the East face. It can only be assumed where the base of the stone is located that it is very near the original position of the stone as set by Henry Meldrum in 1875.



Found stone 14" x 12" x 6" and mound of stone nearly fitting the description in the GLO field notes of Henry Meldrum.

## Description of Monument and Accessories I Established to Perpetuate the Original Location of Corner:

To perpetuate this section corner, at the location of the stone, I set a 2 inch Brass Cap on a 1" x 30" galvanized iron pipe. I buried the pipe to within 8 inches above the ground surface. The original stone was turned upside down and buried on the West side of the new monument with the face of the stone where the marks appear facing the pipe. I then placed a mound of stone and soil three feet in diameter about the monument covering the brass cap. The brass cap monument is stamped as shown in the accompanying photo.



Set brass cap monument to within 8" of the surface in a mound of stone 3 feet at base around monument. Original stone is buried on the West side of monument.

I then set four bearing objects as follows:

Reference No. 1 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears North, 12.00 feet distance. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 2 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears South, 12.00 feet distance and in direct line with bearing object No. 1. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 3 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears East, 12.00 feet distance. Monument pin was driven to within 6 inches above the ground surface.

Reference No. 4 is a 5/8" x 30" iron rebar with an orange plastic cap stamped Reference Monument which bears West, 12.00 feet distance and in direct line with bearing object No. 3. Monument pin was driven to within 6 inches above the ground surface.



Brass Cap as stamped.

This Section corners true geographic position.  
44° 29' 11.92811" N, 117° 53' 27.44767" W NAD83

I, James H. Hambleton certify that this corner was properly reestablished as witnessed by John Eggers on July 26, 2012.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

OREGON  
JULY 10, 1964  
JAMES H. HAMBLETON  
645

Renews June 30, 2014