CERTIFIED RECORD OF LAND CORNER MONUMENTATION


History of Original Corner Establishment:

The original cadastral survey was performed during September of 1881 by George Henderson, Deputy Surveyor, under contract number 409. He set a stone, 14" x 10" x 8" for one quarter section corner, marked 1/4 S on West side with raised mound of stones around the stone.

A retracement survey was performed by Lincoln E. Wilkes, Cadastral Surveyor, dated June 4, 1917. At this corner location, he states he found a Sandstone 14" x 10" x 8", loosely set in a mound of stone; a dimly marked S on one face. He reset the stone 11 inches in the ground and marked a cross (X) on the top of the stone and 1/4 to the north of the cross, with a raised mound of stone 3 feet at base and 2 feet high, north of the corner.

Description of Corner Evidence Found:

Found original Sandstone as described by both Henderson and Wilkes, being 14" x 10" x 8", set firmly in the ground with a cross (X) marked on top of the stone, also a dimly marked 1/4, as well as a clearly marked 1/4 on the north face of the stone, with a somewhat scattered raised mound of stone north of the stone. The upper right photo shows both the dimly marked 1/4 as well as a clearly marked 1/4, showing both Henderson and Wilkes had there hands upon this rock



At the exact location of the cornerstone, I placed a 2 ½ inch brass monument on a 1" x 30" galvanized pipe. The brass cap is about 6 inches above the surface of the ground and stamped as shown in the accompanying photo. I placed the original stone upside down and buried along the north face of the monument. I left the original mound in place, though it is somewhat scattered. I made a mound of stone about the brass cap and flush with top of cap. From which I set one new bearing tree, described as follows:

A Juniper 6 inches in diameter, bears, S 62 15 E, 65.00 feet horizontal distance, blazed and scribed 1/4 S S 28 T 12 S R 41 E BT. I placed a brass washer stamped ORLS 645 at base of blaze. No other trees were available.

Set three Bearing Objects, being 5/8" x 30" iron rebar with orange plastic cap, marked Reference Monument, located as follows:

Bearing object number one bears N 22 00 E, 10 feet distance.

Bearing object number two bears N 62 15 W, 10 feet distance, in direct line and opposite of the new bearing tree.

Bearing object number three bears S 22 00 W, 10 feet distance, in direct line with bearing object number one.



What apears to be a double image, is actually the 1/4 markings of both Henderson in 1881 and Wilkes in 1917.



Corner stone as found in place.



Brass cap as stamped.

R-11

This 1/4 corners Geographic Position: 44 30 06.93886 N, 117 42 02.32388 W, NAD 83.

I, James H. Hambleton certify that this corner was properly reestablished as witnessed by John Eggers on June 6, 2011.

FILED June 28, 2011
BAKER COUNTY SURVEYOR
SURVEY NO. 12-41-6

PROFESSIONAL'
LAND SURVEYOR

OREGON
JULY 10, 1964
JAMES H. HAMBLETON
645

Renews June 30, 2012

1241-6