

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of Original Corner Establishment:

The original cadastral survey was performed during September of 1881 by George Henderson, Deputy Surveyor, under contract number 409. He drove a Juniper post, 3 feet long and 3 inches square, for corner to section 21, 22, 27 and 28, marked T 12 S, S 21 on NW, S 22 on NE, S 28, R 41 E on SW, S 27 on SE faces, with a raised mound of stone around the post.

A retracement survey was performed by Lincoln E. Wilkes, Cadastral Surveyor, dated June 4, 1917. In the retracement of this line, he found the original Juniper post 2 ½ inches square loosely set, marked and witnessed as described by the surveyor general. To perpetuate this corner as follows: at the exact corner point he set a volcanic stone 26" x 12" x 12", 18 inches in the ground for corner of sections 21, 22, 27 and 28 marked with two notches on the south and three notches on the east edges, from which he set:

A Juniper, 16 inches in diameter bears S 00 15 E, 384 links distance, marked T 12 S, R 41 E, S 27, BT.

A Juniper, 8 inches in diameter bears S 63 W, 362 links distance, marked T 12 S, R 41 E, S 28, BT.

No other bearing trees available; placed raised mound of stone 4 feet at base, 2 ½ feet high west of corner.

Description of Corner Evidence Found:

At this section corner location I found a volcanic stone 26" x 12" x 12", set firmly in place as described by Lincoln Wilkes in his 1917 survey. The stone having two notches on the south and three notches on the east faces, with a large mound of stone to the West of corner and a steel fence post driven north of the corner stone. I also found a live Juniper 28 inches in diameter with face partially grown over, scribing visible, which bears S 00 15 E, 384 links distance from found corner. I also found a live Juniper, 19 inches in diameter with face completely grown over, no visible scribing, which bears S 63 W, 362 links distance from found corner. All evidence is in agreement with Lincoln Wilkes notes.



Note: The two notches on the South and three notches on the East edges, though the moss makes them hard to see.

Description of Monument and Accessories I Established to Perpetuate the Original Location of Corner:

I left the original stone and mound undisturbed being firmly in place in very rocky ground. I set a 2 ½ inch brass monument on a 1" x 30" galvanized pipe the base of which is flared, placing it tightly alongside the east face of the original stone and buried to refusal on bedrock, approximately 14 inches deep. I then placed a large mound of stone around the monument and flush with the cap. The brass cap is stamped as shown in the accompanying photo. Both of the original bearing trees are alive and in good condition and remain in place. I set two new bearing trees, described as follows:

A Juniper 10 inches in diameter, bears N 84 E, 41.4 feet horizontal distance, blazed and scribed T 12 S, R 41 E, S 22, BT. I placed a brass washer stamped ORLS 645, at base of blaze.

A Juniper, 16 inches in diameter, bears N 35 15 W, 89.4 feet horizontal distance, blazed and scribed T 12 S, R 41 E, S 21, BT. I placed a brass washer stamped ORLS 645, at base of blaze.



Looking Northwest at original corner stone and mound of stone.

This Section Corners Geographic Position:
44 30 06.56141 N, 117 41 26.96630 W,
NAD 83.



Brass cap as stamped.

R-13

I, James H. Hambleton certify that this corner was properly reestablished as witnessed by John Eggers on June 6, 2011.

FILED June 28, 2011
BAKER COUNTY SURVEYOR
SURVEY NO. 12-41-7

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JULY 10, 1964
JAMES H. HAMBLETON
645

Renews June 30, 2012

12-41-7