

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of Original Corner Establishment:

The original survey was performed during September of 1881 by George Henderson, Deputy Surveyor, under contract number 409. He set a stone 14" x 8" x 8" for the one quarter corner, marked 1/4 S on the West side, with a raised mound of stone around the set stone.

A retracement survey was performed by Lincoln E. Wilkes, Cadastral Surveyor, dated June 4, 1917. In the retracement of this line, he apparently was unable to find the original cornerstone. At the apportioned distance of 39.47 1/2 chains, he set a sandstone 14" x 12" x 8" buried nine inches in the ground for the one quarter section corner marked 1/4 on North face, from which a Juniper 16" in diameter bears N 40 00 E, 127 links distance, and marked 1/4 S, S 22, B.T. No other bearing trees available. Placed a raised mound of stone 3 feet at base, 2 feet high, north of corner.

Description of Corner Evidence Found:

At the corner location, I found a stone 14" x 12" x 8", about 8 inches in the ground, with 1/4 marked on the north face of the stone. I also found a mound of stone on the north side of the corner, that was somewhat fallen apart and scattered. Found a Juniper tree N 40 00 E, 83.83 feet distance or 127 links, agreeing with Lincoln Wilkes' description, however, the tree is now 38" in diameter; the blaze has healed over and only traces of the face are present.



Note: The 1/4 marked on north face of stone.

Description of Monument and Accessories I Established to Perpetuate the Original Location of Corner:

At the exact location of the cornerstone, I placed a 2 1/2 inch brass monument on a 1" x 30" galvanized pipe. The brass cap is about 6 inches above the surface of the ground and stamped as shown in the accompanying photo. I placed the original stone upside down and buried along the north face of the monument. I left the original mound in place, though it be badly scattered. I made a large mound of stone about the brass cap. From which I set three new bearing trees, described as follows:

A Juniper 26 inches in diameter, bears N 54 45 W, 17.25 feet horizontal distance, blazed and scribed 1/4 S 22 T 12 S R 41 E BT. I placed a brass washer stamped ORLS 645 at base of blaze.

A Juniper 3 inches in diameter, bears S 65 00 W, 73.00 feet horizontal distance, blazed and scribed 1/4 S 27 T 12 S R 41 E BT. I placed a brass washer stamped ORLS 645 at base of blaze.

A Juniper 22 inches in diameter, bears S 05 45 E, 60.55 feet horizontal distance, blazed and scribed 1/4 S 27 T 12 S R 41 E BT. I placed a brass washer stamped ORLS 645 at base of blaze.



Looking to the Northeast you can see the original bearing tree and 1/4 corner stone. I placed additional stones around the original marked corner stone.



Brass cap as stamped.

This Section Corners Geographic Position:
44 30 06.44272 N, 117 40 51.05950 W,
NAD 83.

I, James H. Hambleton certify that this corner was properly reestablished as witnessed by John Eggers on June 6, 2011.

FILED June 28, 2011
BAKER COUNTY SURVEYOR
SURVEY NO. 12-41-8

REGISTERED
PROFESSIONAL
LAND SURVEYOR

James H. Hambleton

OREGON
JULY 10, 1964
JAMES H. HAMBLETON
645

Renews June 30, 2012

R-15

12-41-8