

# CERTIFIED RECORD OF LAND CORNER MONUMENTATION

## History of Original Corner Establishment:

The original cadastral survey was performed during September of 1881 by George Henderson, Deputy Surveyor, under contract number 409. He set a stone, 12" x 10" x 5" for Sec. Cor. marked T 12 S, S 29 on NW, S 28 on NE, S 32 R 41 E on SW and S 33 on SE faces; dug pits on each Section line, made raised mound of earth 2 ½ feet high, and 3 feet diameter at base.

A retracement survey was performed by Lincoln E. Wilkes, Cadastral Surveyor, dated June 4, 1917. At this corner, he states he set a volcanic stone 22" x 12" x 8", 16 inches in the ground for corner of sections 28, 29, 32 and 33, marked with one notch on South and four notches on East edges respectively; dug pits 18" x 12" x 12" deep in each section, 5 ½ feet distance from corner.

## Description of Corner Evidence Found:

At the corner location I found a volcanic stone 22" x 12" x 8" located on a steep slope, with very little additional rock present at the location. The stone being very clearly marked with one notch on the south and four notches on the east edge respectively, as shown in the accompanying photo. The ground is quite steep; there were no traces of any pits or mounds of earth alongside.



Cornerstone as found on steep slope.

## Description of Monument and Accessories I Established to Perpetuate the Original Location of Corner:

At the exact location of the cornerstone, I placed a 2 ½ inch brass monument on a 1" x 30" galvanized pipe. The brass cap is about 6 inches above the surface of the ground and stamped as shown in the accompanying photo. I placed the original stone upside down and buried along the west face of the monument. No stone available in this area so a mound of stone was not made at this corner. From which I set two new bearing trees, described as follows:

A Juniper 13 inches in diameter with a double trunk, bears N 30 30 E, 48.90 feet horizontal distance, blazed and scribed T 12 S, R 41 E, S 28 BT. I placed a brass washer stamped ORLS 645 at the base of the blaze.

A Juniper 5 inches in diameter, bears S 24 15 W, 36.60 feet horizontal distance, blazed and scribed T 12 S, R 41 E, S 32 BT. I placed a brass washer stamped ORLS 645 at the base of the blaze.

No other bearing trees were accessible. Therefore I set two bearing objects, being 5/8" x 30" iron rebar with a orange plastic cap affixed to the top, marked Reference Monument, driven to within 6 inches above the surface of the ground and located as follows:

Bearing Object number one is an iron rebar with cap, bears N 40 30 W, 15.00 feet horizontal distance.

Bearing object number two is an iron rebar with cap, placed in direct line with bearing object number one, and bears S 40 30 E, 15.00 feet distance.



A close up view of the stone showing the one notch on the south and four notches on the east edges, being clearly visible and easy to see.



Brass cap as stamped.

This section corners, geographic position.  
44 29 15.31117 N, 117 42 38.64936 W  
NAD 83.

I, James H. Hambleton certify that this corner was properly reestablished as witnessed by John Eggers on June 8, 2011.

FILED June 28, 2011  
BAKER COUNTY SURVEYOR  
SURVEY NO. 12-41-12

v-9

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*James H. Hambleton*

OREGON  
JULY 10, 1964  
JAMES H. HAMBLETON  
645

Renews June 30, 2012

12-41-12