

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of Original Corner Establishment:

The original cadastral survey was performed during September of 1881 by George Henderson, Deputy Surveyor, under contract number 409. He set a stone 12" x 8" x 8" in mound for 1/4 Sec. Cor., marked 1/4 S on the West side, dug pits 20" x 12" x 10" East and West of stone 5 feet distance, and made raised mound of earth 2 feet high, and 2 1/2 feet diameter at base.

A retracement survey was performed by Lincoln E. Wilkes, Cadastral Surveyor, dated June 4, 1917. At this corner, he set a sandstone 23" x 12" x 6", 18 inches in the ground for 1/4 corner of sections 28 and 33, marked 1/4 on North face; placed a raised mound of stone 2 feet at base, 1 1/2 feet high, north of corner.

Description of Corner Evidence Found:

At the corner location I found a sandstone 23" x 12" x 6" firmly set, with only 4 inches protruding out of the ground; located about 5 feet south of a mound of stone. I exposed the faces of the stone, finding it very clearly marked with 1/4 28 on the north face and 33 marked on the south face. The North face is shown in the accompanying photo.



Looking south, the quarter corner stone and original mound is in place as described in GLO notes.

Description of Monument and Accessories I Established to Perpetuate the Original Location of Corner:

At the exact location of the cornerstone, I placed a 2 1/2 inch brass monument on a 1" x 30" galvanized pipe. The brass cap is about 6 inches above the surface of the ground and stamped as shown in the accompanying photo. I placed the original stone upside down and buried along the north face of the monument. I did not disturb the mound of stone found to the north of the monument. I left it in its original position. From which I set two new bearing trees, described as follows:

A Juniper 10 inches in diameter, bears N 04 45 E, 36.50 feet horizontal distance, blazed and scribed T 12 S, R 41 E, 1/4 C, S 28 BT. I placed a brass washer stamped ORLS 645 at the base of the blaze.

A Juniper 12 inches in diameter, bears S 21 45 E, 36.50 feet horizontal distance, blazed and scribed T 12 S, R 41 E, 1/4 C, S 33 BT. I placed a brass washer stamped ORLS 645 at the base of the blaze.

Note: That both bearing trees are the same distance from the monument which is a mere coincidence.

No other bearing trees were accessible. Therefore I set two bearing objects, being 5/8" x 30" iron rebar with an orange plastic cap affixed to the top, marked Reference Monument, driven to within 6 inches above the surface of the ground and located as follows:

Bearing object number one is an iron rebar with cap; bears East, 15.00 feet horizontal distance.

Bearing object number two is an iron rebar with cap, placed in direct line with bearing object number one, and bears West, 12.00 feet distance.



After exposing the north face of the cornerstone, the markings 1/4 28 are clearly visible.



Brass cap as stamped

This one quarter corners geographic position.
44 29 15.16283 N, 117 42 03.10228 W
NAD 83.

I, James H. Hambleton certify that this corner was properly reestablished as witnessed by John Eggers on June 8, 2011.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

James H. Hambleton

OREGON
JULY 10, 1964
JAMES H. HAMBLETON
645

FILED June 28, 2011
BAKER COUNTY SURVEYOR
SURVEY NO. 12-41-13

Renews June 30, 2012