

NARRATIVE CONTINUED

- ① Found marked 16x8x4 inch stone. Replaced with 2 1/2-inch brass cap iron pipe monument in stone mound. Buried original stone one foot north.
- ② Found 3/2-inch brass cap on iron pipe set by Philo H. Anderson, 266 ft. North and 206 ft. East. Did not disturb.
- ③ Found marked stone. Replaced with 2 1/2-inch brass cap on iron pipe monument in stone mound. Buried original stone one foot North.
- ④ Found marked 21x13x12 inch stone. Replaced with 2 1/2-inch brass cap on iron pipe monument in stone mound. Partially buried the original stone one foot North.
- ⑤ Found 3/2-inch brass cap on iron pipe set by Philo H. Anderson 3.54 ft. North and 77.41 ft. East of proper position. Did not disturb.
- ⑥ set 2 1/2-inch brass cap on iron pipe monument, extending 3 inches above ground in a stone mound.
- ⑦ Found Philo H. Anderson's 3/2-inch brass cap on iron pipe RM to C 1/4 corner. His map says monument is 212.8 ft. East of C 1/4 corner. It is 17.28 ft. North and 366.65 ft. East of C 1/4 corner. Did not disturb.
- ⑧ set 2 1/2-inch brass cap on iron pipe monument, extending 4 inches above ground in a stone mound.
- ⑨ set 2 1/2-inch brass cap on iron pipe monument in a stone mound. See narrative for relocation procedure.
- ⑩ Found Philo H. Anderson's 3/2-inch brass cap on bent iron pipe. Anderson did not find the original corner stone and reestablished this location by North-South proportionate measurements only. I am accepting this location because of its long time use and acceptance by other surveys.
- ⑪ ⑫ ⑬ ⑭ ⑮ set 2 1/2-inch brass cap on iron pipe monuments, extending from the ground 4 to 6 inches, in stone mounds.
- ⑯ Found 30x11x9 inch marked stone. Replaced with 2 1/2-inch brass cap on iron pipe monument, extending 5 inches above ground in stone mound. Buried the original stone one ft. East.

THE SOUTH LINE OF SECTION 11, COMPARISON OF BEARINGS:

1. OSHD 8B-30-4 (Lambert)	S. 87° 59' 57" W. 5120.79
2. OREGON PORTLAND CEM. CO. Co. Sur. No. 12-43-3, 1979. (Solar Obs.)	S. 89° 39' 58" W. 5120.83
3. Philo H. Anderson, 1954 & 1959 Not recorded, in ASH GROVE CEMENT WEST, INC. files.	N. 89° 18' 34" W. 5126.89
4. SALT LAKE PIPE LINE CO. files, 1950 not recorded. Their No. A-2459, Sheet 95.	N. 89° 57' 35" W.
5. NORTHWEST PIPELINE CORP files, not recorded Ba. Co. Their No. 1401.1-X-461, 1980.	N. 85° 18' 17" W. 5121.36
6. Now CHEVRON PIPE LINE CO. from pipeline tangent N. 33° 03' W, shown on Ba. Co. Sur. No. 12-43-4, 1983.)	5120.7

MAP OF SURVEY
 SUBDIVISION OF SECTION 11, T. 12 S., R. 43 E., W.M.
 Surveyed Oct. 31, 1984 - Jan. 7, 1985
 For ASH GROVE CEMENT WEST, INC.
 Scale 1" = 400'
 By HANLEY ENGINEERING, Baker, Oregon

FILED Jan. 25 1985

BAKER COUNTY SURVEYOR
 SURVEY NO. 12-43-C

Added Data: 11-25-85
 JDX

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

James D. Hanley
 OREGON
 SEPTEMBER 23, 1977
 JAMES D. HANLEY
 1206