

MONUMENT DETAILS

	<p>Original stone corner was recovered by James D. Hanley, 1972. Survey No. 13-43-1. Remonumented by Dieckmann, 2007: monumented with the original basalt stone, 17 x 9 x 8 ins. (record 16 x 10 x 9 ins.), firmly set, projecting 12 ins. above ground, in a mound of stone, 2 1/2 ft. x 3 ft. base, with no visible marks.</p> <p>Found a 3/4 in. diam. brass cap on 2 1/2 in. diam. iron post, up 4 ins. above ground in 3 ft. diam. by 1 ft. high mound of stone, marked as shown.</p> <p>Corner is on the top of a ridge toward the easterly side.</p>		<p>REFURBISHED</p> <p>Found a 3/4 in. brass cap on a 2 1/2 in. diam. galvanized iron post, leaning at 45° angle with upper 14 ins. exposed, on side area consisting of broken shale rock, all topsoil and plant cover have slid off slope except scattered desert shrubs, marked as shown.</p> <p>A shelf on steep slope was excavated anew around found monument and monument was excavated to base and straightened to original position then stabilized with stones and fill dirt, placed around monument to 6 ins. below top.</p>	<p>From which: I establish the following references:</p> <p>A 5/8 in. diam. by 30 in. long iron rod (rebar) with a 1/2 in. diam. alum. cap, driven 30 ins. in the ground, on small spur ridge approximately 50 ft. above Wly bank of Burnt River, mkd.: ODOT SE, bears S63° 46' 00" E, 222.34 ft.</p> <p>A 5/8 in. diam. by 30 in. long iron rod (rebar) with a 1/2 in. diam. alum. cap, driven 30 ins. in the ground, near top of landslide, mkd.: ODOT SW, bears S03° 37' 15" W, 55.09 ft.</p> <p>NOTE: No suitable area for references in NE and NW quadrants due to landslide.</p>
	<p>Found a granite stone 16 x 8 x 5 inches, lying on surface of the ground, no distinct markings, stone is on shelf on steep 45° slope and near to a collection of large stones and lies at the South end of a N-S line of old standing juniper posts, no wire on posts.</p> <p>At position of found stone: Set a 3 1/4 in. diam. alum. cap on a 5/8 in. diam. by 30 in. long iron rod, driven 20 inches in the ground, on a shelf dug further out of steep slope, placed mound of stone around to top of cap, found stone placed alongside at base, marked as shown:</p> <p>A silver DEEP-1 magnet, buried 4 in. in the ground, bears N25° 46' E, 9.1 ft.</p> <p>A pink DEEP-1 magnet, buried 4 in. in the ground, bears S63° 06' E, 9.8 ft.</p> <p>A blue DEEP-1 magnet, buried 4 in. in the ground, bears S37° 23' W, 9.1 ft.</p> <p>A orange DEEP-1 magnet, buried 4 in. in the ground, bears N72° 27' W, 9.3 ft.</p> <p>NOTE: A juniper post, in place and burned to near ground level, bears N0° 27' 00" W, 42.3 ft.</p>		<p>NOTE: Corner was reestablished C. Albert White, 1964. "The 1/4 sec. cor. of secs. 4 and 33, monumented with the original basalt stone, 17 x 11 x 4 ins., lying on the surface of the ground, mkd. 1/4 on one face."</p> <p>He also states: "From this point a locally established corner bears S. 59° 41' W., 2.03 chs. dist., monumented with a granite stone, 12 x 12 x 9 ins. above ground, firmly set, and in a small mound of stone, mkd. 1/4 on N. face."</p>	<p>Found a 3/4 in. diam. brass cap on a 2 1/2 in. diam. galvanized iron post, up 6 ins., a mound of stone set Northerly has slid downhill, a few stones surround monument, marked as shown.</p> <p>Corner is on a steep north slope.</p>
	<p>Stone in mound of stone, Ira Hoffman, 1929. Stone in mound of stone, Philo H. Anderson, 1933, remonumented by Russell Badgley, 2011.</p> <p>Found a 3/4 in. diam. aluminum cap at ground level, a 1 ft. high mound of stone bears South 1.3 ft., a North-South fence bears west 1.5 ft. Corner is on a small bench on spur ridge.</p>		<p>Found a 2 in. diam. aluminum cap at ground level, marked as shown.</p> <p>Corner is north of Lookout Mt. Road approximately 300 ft., a N-S fence bears West approximately 100 ft., on soil covered slope, no stones or accessories found.</p>	
	<p>Corner was never established.</p> <p>Set a 3/4 in. diam. alum. cap on a 5/8 in. diam. by 30 in. long iron rod (rebar) driven 27 inches in the ground, placed rock collar around monument, with punchmark at center and steel post placed ft. westerly, marked as shown:</p> <p>From which: I establish the following references:</p> <p>A found t-post, antique style with holes along edge, exposed to 23 ins. above ground, bears S73° 49' E, 9.7 ft. (position at base).</p> <p>A blue DEEP-1 magnet, buried 4 in. in the ground, at base of long berm running NWly and SEly, bears S40° 30' W, 11.4 ft.</p>		<p>Found a 3/4 in. diam. brass cap on a 2 1/2 in. diam. steel post, up 6 ins., marked as shown, a mound of stone bears North 1 ft., older mound of stone bears East of corner 5 ft., original stone with visible scribed/next to steel post.</p> <p>Corner is on NWly side of small draw, coursing SWly toward Lookout Mt. Road.</p>	
	<p>Mound of stone, shown on Hwy. drawings, 2B-24-24, 8B-31-9, 10B-22-28 and 10C-44-6 remonumented by Russell Badgley, 2011.</p> <p>Found a 2 in. diam. aluminum cap at ground level, surrounded by rock collar, marked as shown. Center of remnant of mound of stone with survey stake bears West 3 ft. and below on slope.</p>		<p>In the retracement of U.S. Mineral Survey No. 240, I find the largest mine features still distinct and visible on the ground and conforming to the plat and I recover the corner on the lode line common to the On Time and Cleveland quartz claims, said corner originally marked L.S. 2 O.T. on the southwesterly face of a wood post and L.S. 1 C. on the northeasterly face of said post.</p> <p>Found embedded ring of large stones, 3 ft. diameter, approximate size of stones is 12x12x12 ins., from which the collapsed remains of the mouth of tunnel 2 lie at record bearing and distance.</p> <p>Set a 3/4 in. diam. alum. cap on a 2 1/2 in. diam. by 30 in. long alum. post, buried 22 inches in the ground, set a steel t-post Easterly 1 foot, placed mound of stone to top of monument, with punchmark at center of cap, marked as shown.</p>	<p>From which: I establish the following references:</p> <p>A silver DEEP-1 magnet, buried 4 in. in the ground, bears N21° E, 10.0 ft.</p> <p>A pink DEEP-1 magnet, buried 6 ins. in the ground, bears S70° E, 12.7 ft.</p> <p>A blue DEEP-1 magnet, buried 4 in. in the ground, bears S11° W, 9.3 ft.</p> <p>A orange DEEP-1 magnet, buried 4 in. in the ground, bears N86° W, 10.0 ft.</p> <p>NOTE: A 4 strand barb wire fence, running N50° W-S50° E, bears N45° E, 19 ft.</p>
	<p>At position of intersection of Sec. 32 centerlines from reestablished one quarter corners:</p> <p>Set a 3 1/4 in. diam. alum. cap on a 5/8 in. diam. by 30 in. long iron rod, driven 22 inches in the ground, on steep slope in dug out shelf under large sagebrush, placed mound of stone around to top of cap, placed steel post SEly 1.3 ft., marked as shown:</p> <p>From which: I establish the following references:</p> <p>A silver DEEP-1 magnet, buried 4 in. in the ground, bears N61° 18' E, 8.1 ft.</p> <p>A pink DEEP-1 magnet, buried 4 in. in the ground, bears S50° 54' E, 9.0 ft.</p> <p>A blue DEEP-1 magnet, buried 4 in. in the ground, bears S41° 00' W, 7.1 ft.</p> <p>A orange DEEP-1 magnet, buried 4 in. in the ground, bears N61° 10' W, 6.9 ft.</p>		<p>Found a 3/2 in. diam. aluminum cap at ground level, at center of 3 ft. diam. mound of stone, marked as shown.</p> <p>Corner is on an island at split of creek (north fork) above confluence with another branch of creek to the south.</p>	
	<p>Corner was reestablished by C. Albert White, 1964, from found original stone: monumented with the original basalt stone, 14 x 9 x 7 ins., lying in a small mound of stone, mkd. 1/4 on N. face.</p> <p>Found a 3/4 in. diam. brass cap on a 2 1/2 in. diam. steel post, up 2 ins., marked as shown, a mound of stone 4 ft. diameter and 1.5 ft. high bears North 2 ft.</p>	<p>NOTES ON ACCESSORIES</p> <ol style="list-style-type: none"> All bearings shown hereon are true bearings. Corner numbered 13, had accessories taken with hand compass set at 19 1/2° East declination and steel tape Corners numbered 2, 4, 6, 8 and 9 had accessories taken with Leica 1200 GPS system using NAD 83 datum and grid bearings based on SPCS 1983, North zone. True bearings are shown hereon using average convergence angle of 2° 14' 00", positive rotation. 		
	<p>No original evidence of the corner monument was found for this corner. A corner of U.S. Mineral Survey No. 240, the corner on the lode line common to the On Time and Cleveland Quartz Claims, was found and used to reestablish this corner. The field notes for this survey on P. 186 Volume OR-M0009 state: Cleveland Quartz Claim Survey of Lode, Beginning at the previously described L.S. 2 O.T. at the southwesterly end of lode, mark it on north face L.S. 1 C. from which 1/4 section corner between Sections 32 and 33 bears S. 54° W, 3960 feet distant.</p> <p>Set a 3/4 in. diam. alum. cap on a 2 1/2 in. diam. by 30 in. long alum. post, buried 20 inches in the ground, clear DEEP-1 magnet buried alongside at base, placed rock mound around monument to top, set a t-post 1.7 ft. SWly, marked as shown:</p> <p>A 5/8 in. diam. by 30 in. long iron rod (rebar) with a 1/2 in. diam. alum. cap, driven 22 in. in the ground, in fence line on West side of Eastbound lanes of Interstate Hwy. 84, mkd.: ODOT NE, bears N44° 02' 02" E, 86.60 ft.</p> <p>A 5/8 in. diam. by 30 in. long iron rod (rebar) with a 1/2 in. diam. alum. cap, driven 22 in. in the ground, in fence line on West side of Eastbound lanes of Interstate Hwy. 84, mkd.: ODOT SE, bears S58° 25' 03" E, 101.03 ft.</p> <p>NOTE: No suitable area for references in Southwest and Northwest quadrants.</p>		<p>REGISTERED PROFESSIONAL LAND SURVEYOR</p> <p>JAY M. ROUNDTREE 2518 RENEWS: 12/31/2012</p>	<p>OREGON DEPARTMENT OF TRANSPORTATION</p> <p>RETRACEMENT AND R.O.W. MONUMENTATION SECTION 32, T.12S., R.44E., W.M. OLD OREGON TRAIL HWY., INTERSTATE 84 BAKER COUNTY</p> <p>FOR ODOT REGION 5 3012 ISLAND AVENUE LA GRANDE, OR 97850</p> <p>MARCH 26, 2012 SCALE: NTS SHEET 2 OF 3</p>