


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established this survey.



Description of corner evidence found:

A fence corner bears N 26° W, 3.0 ft. dist. from which the fence runs north and east.

Description of monument and accessories established to perpetuate the original location of this corner:

Set a 2½ in. brass cap on a 2 in. iron pipe 31 ins. long and projecting 3 ins. out of the ground with a surrounding rock mound and a six foot steel fence post alongside with a sign 54-9 and 2 signs 54-2 attached.

Brass cap marked thus: T 13 S R 36 E


N $\frac{1}{16}$
 S 33 S 34
 1979
 ORLS 1639

New bearing trees:

A pine 6 ins. diam. bears S 11° E, 10.6 ft. dist. marked N 1/16 S 34 BT
 A pine 6 ins. diam. bears S 61° W, 8.0 ft. dist. marked N 1/16 S 33 BT

Each new bearing tree has a sign 54-3 attached below a band of red paint and has a brass washer marked LS 1639 nailed flush with BT blaze.

I hereby certify that the above corner monument was properly established by me on Oct. 25, 1979 and witnessed by Jim DeNastus and Jeff Townsend.



Office of..... County of.....
 State of....., I hereby certify that the within instrument was filed in this office
 for record on the..... day of....., 19.....
 by
 (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

FILED OCT. 26, 1979
 BAKER COUNTY SURVEYOR
 SURVEY NO. 13-36-13