

T 13 S R 36 E

R.D. Pine

County Baker

Merid. Willamette

N.F. W. W.

State Oregon

## CORNER DIAGRAM

T 13 S R 36 E  
S 21 S 22  
S 28 S 27  
1965  
C S

## DESCRIBE CORNER MONUMENT FOUND

A 2½ in. aluminum cap on a 1 in. iron pipe projecting 18 ins. out of the ground with a surrounding rock mound.

Aluminum cap marked as shown in corner diagram.

## DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

A Pine 50 ins diam with full scribes on open blaze for section 21 BT. This tree is dead.

A Pine 30 ins diam with visible scribes on previously opened blaze for section 22 BT.

A pine 22 ins diam with visible scribes on previously opened blaze for section 27 BT

No trace of section 28 BT

## DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

## PHOTO IDENTIFICATION DATA

Photo No. not ident.

Filed At.

Object Ident.

Ident. By

Signature

## PLANE COORDINATE POSITION DATA

State Zone

X

Y

Estab. By

Agency

Signature *William L. Hanley* Title ORLS 1639

Division

Headquarters

Date

11-16-79

7100-52 (3. 68)

## CORNER RECORD (PERPETUATION)

## MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set the existing aluminum cap monument so that it projects 4 ins. out of the ground and improved the rock mound and set a six foot steel fence post alongside with a sign 54-4 attached.

## ACCESSORIES DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

A pine 14 ins diam bears N 16° W, 33.1 ft dist mkd T 13 S R 36 E S 21 BT.  
A pine 10 ins diam bears S 43° W, 50.5 ft dist mkd T 13 S R 36 E S 28 BT.

Each bearing tree has a sign 54-3 attached below a band of red paint. The new bearing trees also have a brass washer marked PLS 1639 nailed flush with BT blaze.

Work Done By *W. L. Hanley* Title *Land Surveyor* Date *11-16-79* State Registration No. *1639*

Certified Cor. Record Prepared? *Yes* No Filed At:

Date

## REMARKS

Witness: Tom Fisk

Index File No. R 13 T. 13 S R. 36 E WM.

Tract or Surv. No.

Cor. Sec

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William L. Hanley*

OREGON  
JULY 14, 1978  
WILLIAM L. HANLEY  
1639

FILED *July 9, 1982*

BAKER COUNTY SURVEYOR

SURVEY NO. *13-36-53*