

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

A-15

History of original corner establishment:

Corner established by Eugene P. McCornack under contract No. 398 and dated July 02, 1881.

Surveyor General record states:

Set a basalt stone 20x11x10" 15" in the ground for 1/4 sec cor marked 1/4 on N face from which:

A pine 30" diam bears N10°W, 44 lks dist marked 1/4S BT.

A pine 28" diam bears S5°W, 84 lks dist marked 1/4S BT.

DIAGRAM

T 12 S R 36 E

$\frac{1}{4}$ S 34
S 3

T 13 S
1986

ORLS 1639

Description of corner evidence found:

Found a mound of stone with the original stone (broken) marked 1/4.

A pine 29" diam bears S02°30'W (record states S05°W), 84 lks marked 4S on a partially healed blaze.

A pine 30" diam bears N16°30'W (record states N10°W), 44 lks marked 4 BT on open blaze.

Description of monument and accessories I established to perpetuate the original location of this corner:

At position of found stone...

Set 2½" aluminum pipe with 2½" aluminum cap 25" in the ground and surrounded with a mound of earth and stones. Cap marked as shown in corner diagram. Buried stone fragments alongside.

Painted blaze and applied band of red paint around original bearing trees, which were previously signed with signs 54-3 and 54-4. Set steel fence post alongside corner and attached signs 54-2 & 54-9. Compass declination 19° East.

I hereby certify that the above corner monument was properly maintained by me and witnessed by Jim DeMastus on November 04, 1986.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William L. Hanley

OREGON
JULY 14, 1978
WILLIAM L. HANLEY
1639

Office of..... County Surveyor..... County of..... Baker
State of..... Oregon....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....
..... by
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

FILED 1-23-87
BAKER COUNTY SURVEYOR
SURVEY NO. 13-36-61

★ GPO—798-276