

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established by Eugene P. McCornack under Contract No. 398, dated April 02, 1881.

Surveyor General records state:

Set basalt stone 22 x 18 x 5 ins in the ground for 1/4 sec cor marked 1/4 on W face and raise a mound of stone alongside.

A-19

DIAGRAM
T 12 S R 36 E
1/4 S 35
4 S 2
T 13 S R 36 E
1986
PLS 1106

Description of corner evidence found:

None. Searched for 4 hours total on 3 separate occasions with a 2 man crew including 1 PLS. Corner area is on rocky East slope. Someone has searched the area before, turning stones.

Description of monument and accessories established to perpetuate the original location of this corner

Re-established corner by single proportion measure between section corners West and East...

Set 2½" aluminum pipe with 2½" aluminum cap 20" in the ground and surrounded with a mound of earth and stone. Cap marked as shown in corner diagram.

New bearing trees established:

A 12" ponderosa pine bears N28°E, 24.1' scribed 1/4S35 BT.
A 11" ponderosa pine bears S40½°E, 70.9' scribed 1/4S2 BT.

New bearing trees have a brass washer stamped PLS 1106 nailed to face of blaze. Attached sign 54-3 & 54-9 and painted face of blaze and a 6" band around each BT. Set steel fence post alongside corner and attached sign 54-9.

Compass declination 19° East.

I hereby certify that the above corner monument was properly re-established to U.S.F.S. standards under my supervision and witnessed by Willard Hulick on October 29, 1986.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Will. R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of.....County Surveyor.....County of.....Baker.....
State of.....Oregon....., I hereby certify that the within instrument was filed in this office
for record on the day of, 19....., at..... o'clockm., (signed)
..... by
(COUNTY OFFICIAL) (DEPUTY)