

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


History of original corner establishment:

Corner established by Henry W. Cooke under GLO contract no. 528 dated April 10, 1886.

Surveyor General records state:

Set a post $3\frac{1}{2}$ ft long 3 ins square 12 ins in ground for $\frac{1}{4}$ sec cor marked $\frac{1}{4}$ S on W face and raised a mound of stone around post $1\frac{1}{2}$ ft high 3 ft base, there being no trees within limits.

C-13



Description of corner evidence found:

Searched 2 hrs and did not find original post or rock mound, most available rocks are in active fence line rock jacks.

Found old aluminum Forest Service location poster on ground marked as shown. $\frac{1}{4}$ corner is S56°E, 74 lks dist, which was originally attached to a 30" pine that bears N59°W, 60.7'.

R G K
J P
R P
6/7/57

Description of monument and accessories established to perpetuate the original location of this corner

At position determined by single proportionate measurement between adjacent recovered section corners North and South...

Set $2\frac{1}{2}$ " aluminum pipe with $2\frac{1}{2}$ " aluminum cap 24" in the ground and surrounded with a mound of earth and stone. Cap marked as shown in corner diagram.

New bearing trees established:

A ponderosa pine 13" brs N68°E, 80.6' dist marked 1/4S3 BT.

A ponderosa pine 21" brs N59°W, 60.7' dist marked 1/4S4 BT.

New bearing trees have a brass washer stamped PLS 1639 nailed to face of blaze. Attached sign 54-3 & 54-9 and painted face of blaze and a 6" band around each BT. Set steel fence post along-side corner and attached sign 54-9 and 54-2.

Compass declination 19° East.

I hereby certify that the above corner monument was properly established to U.S.F.S standards under my supervision and witnessed by Jim DeMastus on October 22, 1986.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William L. Hanley

OREGON
JULY 14, 1978
WILLIAM L. HANLEY
1639

Office of County Surveyor County of Baker
State of Oregon , I hereby certify that the within instrument was filed in this office
for record on the day of , 19..... , at o'clock m., (signed)
..... by
(COUNTY OFFICIAL) (DEPUTY)