


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

No previous history.

K-15



Description of corner evidence found:

None.

Description of monument and accessories I established to perpetuate the original location of this corner

Corner position established by survey control from recovered corner monument set by J D Hanley marking the corners of the NE $\frac{1}{4}$ section 15, recorded under Baker County Survey No. 13-36-1 filed August 25, 1965...

Set 2 $\frac{1}{2}$ " aluminum pipe with 2 $\frac{1}{2}$ " aluminum cap 25" in the ground and surrounded with a mound of earth and stone. Cap marked as shown in corner diagram.

New bearing trees established:

A juniper 8" dia brs S76 $^{\circ}$ E, 4.6' dist marked CN1/16S15 BT.

A juniper 15" dia brs N17 $^{\circ}$ W, 22.8' dist marked CN1/16S15 BT.

New bearing trees have a brass washer stamped PLS 1639 nailed to face of blaze. Attached sign 54-3 & 54-9 and painted face of blaze and a 6" band around each BT. Set steel fence post along-side corner and attached sign 54-9.

Compass declination 19 $^{\circ}$ East.

I hereby certify that the above corner monument was properly established to U.S.F.S standards under my supervision and witnessed by Jim DeMastus on October 29, 1986.

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

William L. Hanley

OREGON
JULY 14, 1978
WILLIAM L. HANLEY
1639

Office of.....County Surveyor..... County of.....Baker.....

State of.....Oregon....., I hereby certify that the within instrument was filed in this office for record on the day of; 19....., at..... o'clockm., (signed)

(COUNTY OFFICIAL)

by

(DEPUTY)