

**CERTIFIED RECORD OF LAND CORNER MONUMENTATION**

Z-23

**History of original corner establishment:**

Corner established by Eugene P. McCornack under Contract No. 398 and dated July 02, 1881.

Surveyor General records state:

Set basalt stone 18 x 8 x 7 ins 12 ins in ground for 1/4 Sec Cor marked 1/4 on W face and raised stone mound alongside. Pits impracticable.

**DIAGRAM**

T 13 S	R 36 E
<u>1</u>	<u>S 36</u>
4	S 1
T 14 S	
1987	
PLS	1106

**Description of corner evidence found:**

A basalt stone 18 x 8 x 5" (record 18 x 8 x 7") marked 1/4 lying loose in stone mound.

**Description of monument and accessories I established to perpetuate the original location of this corner:**

At position of found original stone...

Set 2½" x 30" aluminum pipe with 2½" aluminum cap 12" in the ground surrounded with a mound of earth & stone. Cap marked as shown in corner diagram. Buried original stone alongside.

New bearing trees established:

A 7" p pine brs S46°E, 148.9' scribed 1/4S1 BT.

A 6" juniper brs N89°E, 80.7' scribed 1/4S36 BT.

New BT's have a brass washer stamped PLS 1106 nailed to face of blaze. Attached signs 54-3 & 54-9 and painted face of blaze and 6" band of red around each BT. Set 6' steel fence post East of corner and attached sign 54-9 and 54-2.

Compass declination 19° East.

I hereby certify that the above corner monument was properly remonumented to U.S.F.S. standards under my supervision and witnessed by Bill Blanford on July 17, 1987.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

EXPIRATION  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

Office of.....County.....Surveyor..... County of..Baker.....  
State of.....Oregon....., I hereby certify that the within instrument was filed in this office  
for record on the..... day of....., 19.....

..... by .....  
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

FILED Sept 28, 1987  
BAKER COUNTY SURVEYOR  
SURVEY NO. 13 36-80

GPO-791-311