

State of Oregon)
County of Baker) ss.

James H. Hambleton


I, _____
do hereby certify that on the _____
day of _____, 19____

I found evidence of the 1/4 Cor.
between sec's 16 & 21
T13S, R36E. W.M.

township _____ range _____
meridian _____

as described hereon; and that from
this evidence I established a new
monument and accessories as
described hereon to perpetuate the
original location of this corner.

*DIAGRAM



Dated at Baker
this 16 day of March, 1968

Signature James H. Hambleton

Title Registered Land Surveyor

Registration No. 645

State of _____)
County of _____) ss.
On this _____ day of _____, 19____

before me, a notary public in and for
said state, personally appeared

_____, known
to me to be the person whose name is
subscribed to the within instrument and
who acknowledged to me that he exe-
cuted the same.

(SEAL) NOTARY PUBLIC

Residing at _____

Commission expires _____

Form R6-5680-182

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

(Reference FSH 5681.65)

History of original corner establishment:

Original subdivision was made during the early part of the year 1886. The survey was made with a mountain transit and chain, through heavy growths of pine, fir, and tamarack with undergrowths of the same.

Set a basalt stone 16 x 12 x 8, 11 ins. in ground for $\frac{1}{4}$ cor. marked $\frac{1}{4}$ on the N. face from which;

A tamarack 40 ins. dia. bears N 45 E, 36 lks. marked $\frac{1}{4}$ S BT.

A pine 24 ins. dia. bears S 45 W, 63 lks. marked $\frac{1}{4}$ S BT.

Description of corner evidence found:

Found a basalt stone 16 x 12 x 8 lying on the surface with the markings $\frac{1}{4}$ scribed on the N face.

Found only the stump of the tamarack 40 in. in dia. checking to the bearing of N 45 E, a distance of 36 lks.

Found alive the pine 24 in. dia. being 30 in. now with the marking $\frac{1}{4}$ S BT. checking to the bearing S 45 W, 63 lks. distance.

Description of monument and accessories I established to perpetuate the original location of this corner

I placed a mound of stone around the $\frac{1}{4}$ stone in the dimensions of 3 feet dia. and $1\frac{1}{2}$ feet high.

I placed a bearing tree tag on the living bearing tree with the distance and bearing scribed on the tag.

I also placed a corner location poster on another tree with the distance and bearing to the $\frac{1}{4}$ cor. scribed on said poster.

Office of County Surveyor County of Baker
State of Oregon, I hereby certify that the within instrument was filed in this office
for record on the 28 day of March, 1968, at 5 o'clock A.M., (signed)
by Tammy Hambleton (DEPUTY)
(COUNTY OFFICIAL)

SURV. 13-36-7