

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established this survey.

**DIAGRAM**

T 13 S R 36 E

C  $\frac{1}{4}$  S 34

Description of corner evidence found:

None

Description of monument and accessories I established to perpetuate the original location of this corner:

Set a 2½ in. brass cap on a 2 in. iron pipe 31 ins. long and projecting 5 ins. out of the ground with a surrounding rock mound and a six foot steel fence post alongside with signs 54-9 and 54-2 attached.

Brass cap marked thus: T 13 S R 36 E

C  $\frac{1}{4}$  S 34

1979

ORLS 1639

New bearing trees:

A pine 8 ins. diam. bears N 23° W, 16.4 ft. dist. mkd C 1/4 S 34 BT  
A pine 6 ins. diam. bears N 43° E, 9.6 ft. dist. mkd C 1/4 S 34 BT

Each new bearing tree has a sign 54-3 attached below a band of red paint and has a brass washer marked LS 1639 nailed flush with BT blaze.

I here certify that the above corner monument was properly established by me on Oct. 25, 1979 and witnessed by Jim DeMastus and Jeff Townsend.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William L. Hanley*

OREGON  
JULY 14, 1978  
WILLIAM L. HANLEY  
1639

Office of..... County of.....  
State of....., I hereby certify that the within instrument was filed in this office  
for record on the..... day of....., 19.....  
..... by .....

(COUNTY OFFICIAL)

(DEPUTY)

Form R6-7100-57 (9/71)

FILED Oct. 26, 1979  
BAKER COUNTY SURVEYOR  
SURVEY NO. 13-36-12