

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established this survey.

DIAGRAM

T 13 S R 36 E

W $\frac{1}{16}$ $\frac{S 34}{S 3}$

T 14 S

Description of corner evidence found:

None

Description of monument and accessories I established to perpetuate the original location of this corner:

Set a 2½ in. brass cap on a 2 in. iron pipe 31 ins. long and projecting 4 ins. out of the ground with a surrounding rock mound and a six foot steel fence post alongside with a sign 54-9 and 2 signs 54-2 attached.

Brass cap marked thus: T 13 S R 36 E

W $\frac{1}{16}$ $\frac{S 34}{S 3}$

T 14 S

1979

ORLS 1639

There being no trees available within limits (trees destroyed by the Stevens Ck. forest fire) I marked a basalt rock 24 x 36 ins. and projecting 14 ins. out of the ground with an X on top and the letters BO on the south face. The rock bears S 42° E, 97.2 ft. dist.

Raised a mound of stone, the nearest point of which bears West, 5.5 ft. dist.

I hereby certify that the above corner monument was properly established by me on Oct. 29, 1979 and witnessed by Jeff Townsend.

Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....

..... by
(COUNTY OFFICIAL) (DEPUTY)

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William L. Hanley

OREGON
JULY 14, 1978
WILLIAM L. HANLEY
1639

Form R6-7100-57 (9/71)

FILED Nov. 1, 1979
BAKER COUNTY SURVEYOR
SURVEY NO. 13-36-18