

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established by Eugene P. McCornack under GLO contract No. 398 dated July 2, 1881.

Surveyor's General records state:

Set a post 3 ft. long 3 ins. square 24 ins. in the ground for 1/4 Sec. Cor. marked 1/4 on W face, from which:

A pine 20 ins. diam. bears S 65° E., 13 lks dist. marked 1/4 S BT
A pine 24 ins. diam. bears N 05° W., 16 lks dist. marked 1/4 S BT

DIAGRAM

T 13 S R 36 E
 $\frac{1}{4}$ $\frac{S \ 34}{S \ 3}$
T 14 S

Description of corner evidence found:

A burned pine 24 ins. diam. with full scribes on partially healed blaze Section 3 bearing tree.

A burned pine 26 ins. diam. with visible blaze but no scribes identified for Section 34 bearing tree.

These record bearing trees were burned by the Stevens Creek forest fire. The section 34 bearing tree is obviously dead but the section 3 bearing tree may possibly have survived.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set a 2½ in. brass cap on a 2 in. iron pipe 31 ins. long and projecting 3 ins. out of the ground with a surrounding rock mound and a 6 foot steel fence post alongside with a sign 54-4 attached.

Brass cap marked thus: T 13 S R 36 E

$\frac{1}{4}$ $\frac{S \ 34}{S \ 3}$

T 14 S

1979

ORLS 1639

There being no trees available within limits (trees destroyed by Stevens Creek forest fire) I marked the following bearing objects:

A basalt boulder 4 x 6 ft. and projecting 6 ft. out of the ground bears N 79° W, 212.7 ft. dist. marked X DO.

A basalt boulder 2 x 3 ft. and projecting 2 ft. out of the ground bears S 81° W, 243.5 ft. dist. marked X DO.

I hereby certify that the above corner monument was properly re-established by me on November 6, 1979 and witnessed by Jeff Townsend.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William L. Hanley

OREGON
JULY 14, 1978
WILLIAM L. HANLEY
1639

Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....

..... by
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

FILED Nov. 8, 1979

BAKER COUNTY SURVEYOR
SURVEY NO. 13-36-21