

**CERTIFIED RECORD OF LAND CORNER MONUMENTATION**

Index File No. E-23

**History of original corner establishment:**

Corner was originally established under G. L. O. contract No. 398 by E. P. McCornack, on September 10, 1881. Surveyors General's notes state: "Set Basalt stone 15 X 12 X 3 ins. 10 ins. in the ground for 1/4 sec. cor. marked 1/4 on W. face and raised a mound of stone alongside."

**DIAGRAM**

T13S R36E  
S 1  
1/4 — I —  
S 12

**Description of corner evidence found:**

Found an 18 X 9 X 3 inch stone marked 1/4 and mound of stone on the West side.

**Description of monument and accessories I established to perpetuate the original location of this corner:**

At the center of the above stone set 2 1/2" X 30" galvanized pipe and brass cap marked:  
Set pipe 24" in the ground and mound of stone around to cap.

T13S R36E  
S 1  
1/4 — I —  
S 12  
OR PLS 1051  
1982

**REGISTERED  
PROFESSIONAL  
LAND SURVEYOR**

*Barry B. Barbour*

OREGON  
OCT. 17, 1975  
**BARRY B. BARBOUR**  
1051

I hereby certify that the above corner monument was reestablished as herein described.

Witnesses: Daniel Rowland  
Kenneth Alexander

April 19, 1982

Office of.....County Surveyor.....County of.....Baker  
State of.....Oregon....., I hereby certify that the within instrument was filed in this office  
for record on the.....21st day of.....April....., 19..82  
..... by .....  
(COUNTY OFFICIAL) (DEPUTY)

**Form R6-7100-57 (9/71)**

FILED April 21, 1982

BAKER COUNTY SURVEYOR

SURVEY NO. 13-36-52